EC

CORPS OF ENGINEERS, U. S. ARMY

SURGES IN SOUTHERN OUTFALL SEWER AND FLOW CONDITIONS IN STATE FAIRGROUNDS (WESTERN PARKWAY) PUMPING PLANT LOUISVILLE, KENTUCKY

HYDRAULIC MODEL INVESTIGATION



TECHNICAL MEMORANDUM NO. 2-367

CONDUCTED FOR

LOUISVILLE DISTRICT, CORPS OF ENGINEERS

BY

WATERWAYS EXPERIMENT STATION

VICKSBURG, MISSISSIPPI

ARMY-MRC VICKSBURG, MISS.

JUNE 1954

PROPERTY OF U. S. ARMY OFFICE CHIEF OF ENGINEERS LIBRARY

maintaining the data needed, and c including suggestions for reducing	lection of information is estimated to ompleting and reviewing the collect this burden, to Washington Headqu ald be aware that notwithstanding an OMB control number	ion of information Send comment arters Services, Directorate for Info	s regarding this burden estimate ormation Operations and Reports	or any other aspect of the s, 1215 Jefferson Davis	his collection of information, Highway, Suite 1204, Arlington	
1. REPORT DATE JUN 1954		2. REPORT TYPE		3. DATES COVE 00-00-1954	ered 4 to 00-00-1954	
4. TITLE AND SUBTITLE				5a. CONTRACT	NUMBER	
Surges in Southern Outfall Sewer and Flow Conditions in State Fairgrounds (Western Parkway) Pumping Plant, Louisville, Kentucky:			5b. GRANT NUMBER			
Hydraulic Model Investigation			5c. PROGRAM ELEMENT NUMBER			
6. AUTHOR(S)				5d. PROJECT NU	JMBER	
				5e. TASK NUMBER		
				5f. WORK UNIT	NUMBER	
	ZATION NAME(S) AND AE f Engineers,Waterv ourg,MS,39180	` '	ntion,3903 Halls	8. PERFORMING REPORT NUMB	G ORGANIZATION ER	
9. SPONSORING/MONITO	RING AGENCY NAME(S) A	ND ADDRESS(ES)		10. SPONSOR/M	IONITOR'S ACRONYM(S)	
				11. SPONSOR/M NUMBER(S)	IONITOR'S REPORT	
12. DISTRIBUTION/AVAIL Approved for publ	ABILITY STATEMENT ic release; distributi	on unlimited				
13. SUPPLEMENTARY NO	TES					
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFIC	ATION OF:		17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON	
a REPORT unclassified	ь abstract unclassified	c THIS PAGE unclassified	Same as Report (SAR)	119		

Report Documentation Page

Form Approved OMB No. 0704-0188

pours

CORPS OF ENGINEERS, U. S. ARMY OFFICE OF THE DIRECTOR WATERWAYS EXPERIMENT STATION VICKSBURG, MISSISSIPPI

WESDR

23 JUN 1954

Transmittal of T. M. 2-367, "Surges in Southern Outfall Sewer and

Flow Conditions in State Fairgrounds (Western Parkway) Pumping Plant, Louisville, Kentucky; Hydraulic Model Investigation."

TO:

The Chief of Engineers (ENGKW)

Department of the Army Washington 25, D. C.

T. M. 2-367, "Surges in Southern Outfall Sewer and Flow Conditions in State Fairgrounds (Western Parkway) Pumping Plant, Louisville, Kentucky; Hydraulic Model Investigation," is forwarded herewith for your information and retention.

fincl (in dup) T. M. 2-367

C. H. DUNN Colonel, Corps of Engineers

Director

PREFACE

Model studies of surges in the Southern Outfall Sewer and of flow conditions in the State Fairgrounds Pumping Plant*, Louisville, Kentucky, were authorized by the Chief of Engineers, Department of the Army, in second indorsement dated 6 February 1947, to a letter from the District Engineer, Louisville District, CE, dated 15 January 1947. Model studies were conducted in the Hydraulics Division of the Waterways Experiment Station during the period December 1947-July 1950. Personnel actively connected with the model study were Messrs. F. R. Brown, T. E. Murphy, T. J. Buntin, and G. B. Sims.

Messrs. C. L. Cowan, J. R. Hamilton, and R. E. Karlen of the Louisville District, and Mr. R. L. Irwin of the Ohio River Division, visited the Waterways Experiment Station to discuss test results and to correlate these results with design work being carried on concurrently in the District Office. Messrs. F. U. Druml and H. B. Willis** of the District and Irwin** did all the analysis work in the application of the model data to the prototype problem. This work is summarized in appendices A and B to this report.

^{*} Name of plant later changed to Western Parkway Pumping Plant.

^{**} Presently of the Office, Chief of Engineers, and Washington District, respectively.

CONTENTS

•			Page
PREFACE .			. i
SUMMARY .			. v
PART I:	TRODUCTION		. 1
Pert	roblem	• •	. 1 . 2 . 4
PART II:	HE MODELS		• 5
Desc	n Considerations		_
PART III:	NARRATIVE OF TESTS — SURGE MODEL		. 10
Wate Sur	minary Tests of Model Construction Materialhammer Pressures in Sewer		
PART IV:	ARRATIVE OF TESTS — PUMPING PLANT MODEL		. 17
Oria Deve	Conditions	• •	17171924
PART V: I	SCUSSION OF TEST RESULTS		. 26
	Model	• •	2627
TABLES 1-3			
PLATES 1-2			
APPENDIX A	DEVELOPMENT OF ANALYTICAL METHOD FOR DETERMINATION OF SURGES IN SEWERS	TION	.Al-A3
PLATES Al-	4		
APPENDIX I	ANALYSIS OF SURGES IN SOUTHERN OUTFALL SEWER (PROTOTYPE)		. Bl
Sout Plar Gene Meth Surg	al	• • •	B1 B2 B3 B4 B6 B6 B7

CONTENTS (Cont'd)

APPENDIX B:	ANALYSIS OF (PROTOTYPE)		SOUTHERN	OUTFALL	SEWER		
	ility of Sure	-					_
PLATES B1-B5		~					

SUMMARY

Model investigations of the surges occurring in sewer lines and of the flow conditions in a typical pumping plant, used to dispose of drainage during high river stages, were conducted as a part of the local floodprotection project for Louisville, Kentucky. Studies conducted on a 1:32scale simplified model of the Southern Outfall Sewer provided general information on the relative amount of relief from surges to be expected from the pumping station and manholes in the sewer line upstream. It was determined that the open sump absorbed all water-hammer effects with no increase in pressure occurring upline from the sump. It also was determined that the time of valve closure (pump stoppage) had little effect upon the maximum height of surge rise. A decrease in the size of the sump increased the maximum height of rise; an increase in the area of the risers had little or no effect on the height of rise, although increasing the area greatly lengthened the time of rise. The height of surge upline was reduced by allowing one of the lower manholes to be overtopped and the excess water to go into storage above ground. time of concentration tests indicated that with a surcharged sewer the time of travel of an additional increment of water from the point of entry to the point of exit was practically instantaneous; whereas, with a sewer flowing partially full, the additional increment traveled with the normal velocity of the water, thus greatly increasing the time of concentration of flow at the lower end of the sewer. The above studies provided data that formed the basis for a comprehensive analysis of the surge problem in sewers.

Tests of the State Fairgrounds Pumping Plant were made on a 1:16-scale model and provided information on plant performance for gravity and pumped flow. Flow conditions were improved throughout the plant by revising the intake and outlet transitions and removing the baffle walls in the discharge channel. It was determined from the model studies that an approximate depth of 2 ft of water was required over the lower end of the inlet transition to prevent the passage of air upstream resulting from surges in the main sump.

SURGES IN SOUTHERN OUTFALL SEWER AND

FLOW CONDITIONS IN STATE FAIRGROUNDS (WESTERN PARKWAY) PUMPING PLANT LOUISVILLE, KENTUCKY

Hydraulic Model Investigation

PART I: INTRODUCTION

The Problem

1. The city of Louisville, Kentucky, is located on the left bank of the Ohio River, approximately 200 miles northeast of the river's mouth

(fig. 1). At present the city's sanitary sewage and the storm water drainage both empty into the Ohio River through a series of combined sewer systems. These systems are of the gravity flow type, and no pumping facilities are provided for forcing the sanitary sewage and storm water into the river during flood stages. Accordingly, it is proposed to build a series of pumping stations near the outlet ends of existing sewer systems or on diversion sewers to pump sewage and runoff across the




Fig. 1. Vicinity map

line of protection into the river during flood stages.

2. Preliminary design of the internal drainage facilities of the city of Louisville indicated that, in several instances, pumping stations would be operating with a considerable length of sewer flowing under a surcharge. It appeared that any sudden change in pump discharge, such as might be caused by a power failure, while the station was operating under a surcharge would create surges in the sump which might result in serious damage to the system. This surge problem is apparently analagous to that of a penstock, although the mathematical

solution in connection with sewers is more difficult because of the numerous inlet points and the frequent changes in sewer size. The need for information on surge effects was considered critical enough by the Ohio River Division that studies having application to the Louisville internal drainage problem were initiated. These tests were extended to include the study of flow conditions at the entrance to and through a typical pumping station.

Pertinent Features of the Prototype

- 3. The Southern Outfall Sewer System* was selected by the Louis-ville District, CE, as the prototype on which to base the model. This system drains an area of about 4,540 acres, and has a total length of main-line sewer of approximately 33,000 ft (fig. 2) with accompanying laterals and manholes. The main sewer is of concrete construction, varying from a 5-ft-3-in. semielliptical shape to a 15-ft-6-in. horseshoe shape. The surcharged capacity of the sewer is approximately 1700 cfs.
- 4. A pumping plant (plate 1), designated as the State Fairgrounds Pumping Plant, is to be constructed at the lower end of the Southern Outfall Sewer line for disposal of storm water when the river elevation is higher than that of the sewer. The plant will be constructed of concrete with top of discharge chamber at elevation 462**, and is designed to carry a flow of 1800 cfs when the river is at elev 427.2, and 910 cfs when the river is at elev 458.3. Capacities for model testing were 1800 cfs at river elev 430 and 1200 cfs at river elev 458.3. The average velocity in the sewer during the maximum flow will be approximately 20 ft per sec. The pumping plant was planned to be constructed in an off-set position from the existing concrete horseshoe-shaped sewer, which is 10 ft 7 in. by 10 ft 1-1/2 in., and connected to the existing sewer by a transition on each end. The final design provides for "over-sewer" location. The upper transition will be flared so as to decrease the velocity of flow before it enters the sump chamber. The storm-water

^{*} See appendix B for more detailed descriptions of sewer system.

^{**} All elevations are in feet above mean sea level.




Fig. 2.

pumps will be open-pit type installations with each intake opening into a trash rack well. Each trash rack well will be connected to the sump chamber by a gated opening. The pump installation tested consists of four 1500-hp (386 cfs) pumps and two 500-hp (128 cfs) pumps. Final design of this pumping plant provides for four 1250-hp (360 cfs) and three 500-hp (120 cfs) pumps. The river end of the sump chamber will be connected through two gated openings to the outfall sewer, so that the transition section and sump chamber will serve as a part of the gravity outlet of the sewer when the pumping plant is not in operation.

5. It is proposed to maintain the water-surface elevation in the sump chamber within a 5-ft range when the pumps are operating. The pumps will be manually controlled and turned on consecutively, starting with the riverward pump and progressing landward.

Purposes of the Model Studies

6. Two models were considered necessary to study the principal problems involved in designing an efficient and safe sewer system and pumping plant for the conditions existing at Louisville. A simplified model of a part of the main-line sewer is designated in this report as the "surge model" since it was used to determine (a) the water-hammer pressures in the main-line sewer, (b) the surges that might occur at the pumping plant and in the lower reaches of the connecting sewer, and (c) the effects of surcharging the sewer upon the time of concentration of flows at the pumping station. Results of tests from the simplified model could not be applied directly to the Louisville sewer system but were to be used to evaluate the effects of certain variables as a basis for a more comprehensive mathematical development of the design. The second or "pumping plant model" was used to study flow conditions in and through the pumping plant for gravity and pumped flow.

5

PART II: THE MODELS

Design Considerations

- 7. Considerable attention was given to the selection of the type models that would allow the desired data to be obtained with minimum expense. After all factors involved had been carefully weighed, it was decided that a simplified model of a portion of the main sewer and the more important laterals would permit collection of data that could be applied analytically to the over-all sewer design. A 1:32 scale was selected for the surge model. Its use permitted the cross-sectional area of the lower part of the main sewer to be simulated by means of a 6-in.-diameter circular pipe; a 4-in.-diameter circular pipe simulated the 10-ft horseshoe-shaped section of sewer in the vicinity of the pumping plant. A 1:16 scale was selected for the pumping plant model in order to permit more detailed study of the flow conditions in the sump and transition areas.
- 8. Fluid motion in both models was effected predominantly by the force of gravity, which permitted the variation of all hydraulic quantities in their proper relationships as derived from the Froude law. Since it was desired to reproduce water-hammer phenomena in the surge model, and since the velocity of propagation of a pressure wave is a function of the elasticity of the fluid medium and of the conduit walls, elastic forces were also a factor for consideration and Cauchy's number was of primary importance. Therefore, in order to insure closer relationships with regard to elastic forces, the model sewers were constructed of plastic. This material possesses the elasticity required to bring the velocity of pressure-wave propagation about into consonance with the Froudian velocity scale governing discharge in the model.* The use of plastic tubing also aided in approximating the desired roughness values. Relationships for transference of model data to prototype equivalents,

^{*} For verification see Waterways Experiment Station TM No. 185-1, "Model Study of Hydraulic Characteristics of Power Tunnel, Fort Peck Dam," November 1941.

or vice versa, are listed in the following tabulation where the subscript represents the model-to-prototype ratio:

		Scale Relationship		
Dimension	Ratio	Surge Model	Pumping Plant	
Length	L	1:32	1:16	
Area	$A_r = L_r^2$	1:1024	1:256	
Time	$T_r = L_r^{1/2}$	1:5.66	1:4	
Velocity	$V_r = L_r^{1/2}$	1:5.66	1:4	
Discharge	$Q_{r} = L_{r}^{5/2}$	1:5793	1:1024	
Roughness	$n_r = L_r^{1/6}$	1:1.782	1:1.586	

Description

- 9. The 1:32-scale model reproduced approximately 10,000 ft of the lower part of the main line of the Southern Outfall Sewer (fig. 3 and plate 2). No laterals or risers were reproduced initially; however, provision was made for installing a short section of each of five main laterals during the testing program. The entire model was constructed initially of 6-in. plastic tubing (model); after the initial tests the lower 1600 ft was replaced by 4-in. tubing (model). The wall thickness of the 6-in. and 4-in. plastic tubing was 1/8 in. and 1/4 in., respectively. The pumping plant was represented in this model by a rectangular, plastic box equal in area to the sump chamber. The sudden stoppage of flow was produced in the surge model by means of a quick-closing valve on which an electrical measuring device was installed so that the length of time required to effect closure could be measured and recorded. Sections of plastic tubing for reproducing the risers or manholes were provided for installation when required.
- 10. The 1:16-scale model of the State Fairgrounds Pumping Plant reproduced approximately 175 ft of the existing sewer upline from the pumping plant; the entire pumping plant, including the intake and outlet transitions; and approximately 45 ft of the existing and proposed sewers below




Fig. 3. Model of Southern Outfall Sewer




Fig. 4. Model of State Fairgrounds Pumping Plant

the pumping plant (fig. 4 and plate 3). The sewers and pumping plant were constructed of plastic. Pump action was produced in the pumping plant model by six separate outflow and inflow lines, the pumping force being supplied through common headers by means of a 3-cfs centrifugal pump. Each pair of lines was equipped with a circular orifice plate and valve so that any desired combination of discharges could be set up in the system. River stages were simulated initially by means of a valve installed in the discharge line. This model was later revised so as to reproduce the extension of the proposed and existing sewers to the river, and stages were maintained by means of a tailbay into which the sewers emptied (fig. 5).

Appurtenances

11. The inflow into both models was measured by means of venturi

meters. An overflow weir was provided in the headbay of the surge model to carry off the excess water upon sudden stoppage of flow.

12. Static pressures were measured by means of water piezometers and water-surface elevations were read by means of staff gages. Velocities in the sewers were measured by means of a pitot tube mounted in a special collar which permitted attachment of the tube to the pipe at any desired location. Pressures due to water hammer were measured by means of pressure cells connected to an oscillograph recorder (fig. 6). The pressure cells were of the electromagnetic type developed at the



Fig. 6. Recording apparatus




Fig. 5. Tailbay wherein water level could be controlled to simulate river stages

Waterways Experiment Station for the measurement of fluid pressures. A continuous photographic record of the pressure fluctuations was obtained; plate 4 shows typical oscillograph records.

13. Surges were measured by two methods. Initially they were measured by means of resistance gages installed in risers and in the sump and were recorded by means of an oscillograph. In later tests the maximum height and time of rise of the surges were obtained by visual observation and a stop watch, respectively.

PART III: NARRATIVE OF TESTS -- SURGE MODEL

Preliminary Tests of Model Construction Material

- 14. A preliminary series of tests was conducted to verify the assumptions made during the design of the model to satisfy the requirements of Cauchy's number. These tests involved: (a) determination of the speed of propagation of the pressure wave along the plastic tube with the entire length of sewer constructed of 6-in.-diameter plastic tubing; (b) determination of the coefficient of roughness of the plastic tubing. Pressure wave propagation
- 15. The modulus of elasticity of the 1/8-in.-thick plastic material (Lucite) used for the model sewer was determined to be 392,000 lb per sq in. A check of this value after completion of the tests indicated that the modulus remained unchanged. The velocity of propagation of the pressure wave in the prototype was computed to be about 3760 ft per sec; thus the corresponding theoretical pressure wave in the model was approximately 660 ft per sec. The 6-in.-diameter, 1/8-in.-thick Lucite tubing was estimated to be capable of accommodating a velocity of pressure wave propagation of 766 ft per sec, assuming the tubing to be continuous with no joints. However, the model sewer was constructed of 4-ft sections of tubing with a 1-1/2-in. plastic flange on the end of each section. If the entire model had been constructed of plastic with a wall thickness of 1-1/2 in., the pressure wave velocity would have been about 2330 ft per sec. The introduction of a correction factor based upon the number of flanges on the tubing as a proportion of the total length of the model sewer permitted an upward revision of the expected velocity of pressure wave propagation to about 925 ft per sec. This velocity agreed closely with the measured velocity of 1000 ft per sec. the actual value of the velocity of pressure wave propagation (1000 ft per sec) was somewhat in excess of the velocity (660 ft per sec) required for satisfying exact similitude requirements.
- 16. The model was initially constructed with short stub pipes at each of the riser locations. These stubs were capped, thus providing a

series of branching dead-end pipes. The first tests indicated that the sudden closure of the valve at the pumping plant resulted in a constantly increasing pressure from the valve toward the headbay. This condition was caused by the reflection of pressure waves from the dead ends of the small branching pipes which in turn increased the pressure in the main sewer. Plugs inserted flush with the main sewer in these branch pipes equalized shock pressures along the sewer line.

Coefficient of roughness

17. The coefficient of roughness of the plastic model sewer was determined from Manning's formula and is presented on plate 5. The computed average velocities based on the flow through the sewer were used in the computation of roughness values. The slope of the hydraulic gradient was determined from piezometers located along the model sewer.

Water-hammer Pressures in Sewer

- 18. Initial tests to determine water-hammer pressures were made with the entire length of sewer constructed of 6-in. plastic tubing. No laterals or risers were installed and all short stub connecting pipes were plugged as described in paragraph 16. The quick-acting closing valve was located at the end of the sewer section with no intervening sump chamber. Pressures were recorded at six locations along the sewer (plate 2) for discharges of 1400, 1800, and 2000 cfs prior to stoppage of the flow. Results of these tests (plates 6-8) indicated that a maximum pressure of approximately 450 lb per sq in. existed at all points for conditions of maximum discharge. Pressures decreased as the discharge prior to valve closure was decreased.
- 19. The lower 50 ft of the 6-in. tubing was replaced by 4-in. tubing in succeeding tests and the magnitude of the pressure wave was again measured for flows of 1400, 1800, and 2000 cfs with instantaneous valve closure. The maximum pressures in the 4-in. line were approximately 2200 lb per sq in., whereas the maximum pressures in the 6-in. line upstream were only about 750 lb per sq in. (plates 9-11). A comparison of the pressures obtained at the three discharges is shown in table 1. Variation in the

length of time of closure of the valve to determine the effect on waterhammer pressures in the line revealed that for a closure time in excess of 40 sec the resulting water-hammer pressures were negligible.

Surges in Sump of Pumping Station and Sewer

Effect of sump installation

20. A chamber reproducing to scale the proper dimensions and area of the prototype sump of the pumping station was installed in the model. The surge relief flap openings, located near the top of the sump, were not reproduced initially and the chamber was constructed to sufficient height to prevent overtopping (fig. 7). Since the actual time of stoppage




Fig. 7. Sump chamber with surge relief valves and pump outlets

of the prototype pumps was unknown, it was assumed that the time of stoppage would probably not exceed 2 minutes. A series of tests with discharges of 1400, 1800, and 2000 cfs was made and the time of stoppage varied from 1 to 156 seconds (table 2). It may be noted from this table that the maximum height of rise of the water surface in the sump chamber varied only slightly regardless of the length of time required to close the valve (pump stoppage). Coincidental with these tests, measurements of the water-hammer pressures existing upline from the sump were also made.

These measurements indicated the high pressures noted previously within the closed sewer system upstream were completely relieved by the sump chamber and were in the same range as the height of rise of water in the sump.

Effect of relief openings and pump outlets

21. The height of rise of water in the sump chamber, as described

in the preceding paragraph, exceeded the prototype elevation of the top of the sump (elev 462). Therefore, it was desired that the effect of the surge relief openings and the pump outlets on the water-surface elevation be studied. Accordingly, the 60-in. relief flap gates were reproduced, seven with a center-line elevation of 452.0 and one with a center-line elevation of 455.5. Tests were made for varying times of stoppage for flows of 1400, 1800, and 2000 cfs. The height of rise of the water level in the sump chamber was greatly reduced from heights previously measured (table 3). Some relief also will probably result from flow through the pump inlets and into the outlet channel even though the pumps are stopped. As the pump impellers and fittings will offer considerable resistance to this flow, the assumption was made that each pump outlet would have an effective area of 50 per cent of its actual area. Openings of the desired size were made in the sump walls at the proper elevations. The previous tests were repeated and, as expected, the height of rise of the water level in the sump chamber was reduced still further (table 4).

Effect of risers (manholes)

22. The five principal manholes in the section of sewer included in the model limits were simulated by the addition of a vertical riser installed in the correct location. The relief openings and pump outlets in the sump chamber were closed and the number of risers was increased one at a time in succeeding tests. The maximum height of water level in the sump and individual risers was measured for flows of 1400, 1800, and 2000 cfs (tables 5-6). Complete hydrographs of the surge in the sump and risers were obtained (plate 12). To study the effect of the initial sump stage on the height of rise, tests were also conducted with the initial sump stage varied over a range of approximately 25 ft. These tests revealed that water-surface elevations in the sump and risers were parallel and varied as the difference in elevation between initial sump stages. Thus the surge rise in feet was the same, regardless of the sump stage at which flow stoppage was accomplished. The stoppage of only one or more of the large pumping units also could cause a surge in the sump chamber and risers. Accordingly, tests were made simulating the closure of individual and combinations of pumping units. The maximum heights of these

surges are listed in table 7. As to be expected, an increase in the amount of flow stoppage increased the amount of surge in the sump chamber and in the sewer upstream.

Variation in sump area

23. Tests were made with sump areas of 700, 1400, and 2100 sq ft to study the effect that variation of the area of the sump would have on the height of rise of water level in the sewer line caused by a stoppage of the pumping units. Results of these tests (tables 8-10) indicated that the height of rise was greatly increased by decreasing the area of the sump.

Submergence of sump outlets

24. The tests previously described were made with the pump outlets and relief flap valves open to atmospheric pressure. In the prototype, however, the head against which the pumps will operate could be above the pump outlet. Therefore, in an attempt to simulate the effect of an increase of the river stage on the surge relief through the pump outlet lines, the pump openings in the sump chamber were raised to the same elevation as the flap relief valves (elev 452.0). This increase in elevation had the same effect as increasing the river stage. The area of pump openings was decreased 50 per cent as in previous tests. Tests were made for flows of 1100, 1400, 1600 cfs as requested by representatives of the Louisville District. Results are listed in table 11.

Dispersion of inlet flow

- 25. For all previously described tests, the total inflow was introduced into the upper end of the model. To investigate the effect of dispersion of the inlet flow, a total flow of 1800 cfs was distributed between the five main laterals included in the model. The sudden stoppage of flow at the pumping plant resulted in an increase in water level in the sump and risers (table 12) which agreed closely with the results obtained when the total flow was introduced at the upper end of the model. Storage of surge flow
- 26. All previously described tests with the risers installed were conducted with the surge flow contained within the risers. To study the effect of permitting the risers to overflow and containing the water in

storage reservoirs, the riser nearest the sump chamber (point 21) was cut off at elevations of 440, 438, and 436 ft in successive tests. For each elevation of top of the riser and the complete stoppage of a flow of 1800 cfs, the maximum elevation attained by the surge in each of the other risers was measured. These tests indicated that lowering the top of this riser from elev 440 to 436 had no effect on the elevation of the surge in the other risers (table 13). However, the reduction in the elevation of the riser from that required to prevent overflow to 440 resulted in a considerable reduction in the maximum elevation of the surge in the risers upline.

27. Tests were also made for the three riser elevations with the flow only partially stopped. These tests simulated the stoppage of one of the 1500-hp pumping units. Under these conditions, only a slight rise in water level was caused in the risers of the sewer line. The riser at point 21 was overtopped very slightly when it was cut off at 436.0 (table 14).

Area of risers

28. In tests to determine the effect of area of risers on the surge the area of each of the five risers or manholes reproduced on the model was increased from 50.68 sq ft (prototype) to 201 sq ft. The height of surge was then measured in each riser for flows of 1400, 1800, and 2000 cfs. The maximum height of surge attained was approximately the same as that obtained with the smaller riser. However, the time required for the surge to reach this elevation was increased (table 15).

Time of Concentration

29. It was realized that the time of concentration of flows could not be simulated for the entire Louisville sewer system, since the model reproduced only a small part of the over-all sewer system. However, it was considered probable that some indications of the relative characteristics of the times of concentration for partially full and for surcharged sewers could be demonstrated by the model. The tests to investigate the time of concentration were made in two phases.

- 30. The first-phase tests were conducted with the sump and all risers installed. An initial discharge of 1100 cfs was used and the sewer was flowing partially full. A sudden increase in flow was introduced at the upper end of the sewer and the time that elapsed before the discharge increased at the lower end was noted. This test was repeated with the sewer initially surcharged (flowing full) by a flow of 1800 cfs. The elapsed time before increased flow was noted at the pumping station in the partially full sewer was 119 sec (prototype), whereas in the surcharged sewer it was only 28 sec.
- The second phase of the time-of-concentration tests was made with the risers removed and all openings sealed, thus providing a closed conduit from the upper end of the model to the sump. An initial flow of 750 cfs was introduced into the model so that the 6-in. (model) pipe was about one-third full and the 4-in. (model) pipe was about one-half full. The flow of water was suddenly increased as before and the time for increased flow at the pumping plant was measured. The sewer was then surcharged as before and the time of travel of the additional water again measured. The time of travel for the low flow was 351 sec (prototype) and for the high flow it was less than 6 sec. Thus, it would appear that for conditions of a surcharged sewer system, increases in flow at widely separated areas would be reflected almost instantaneously at the pumping The time of concentration would be affected slightly by the number of manhole openings but not to the degree expected. This factor is important in the determination of the design of pumping capacity for the plant.

PART IV: NARRATIVE OF TESTS -- PUMPING PLANT MODEL

Test Conditions

32. Tests on the 1:16-scale model of the pumping plant (fig. 8) were made for conditions of both gravity and pump flow. During initial tests the outflow was controlled by a valve located in the discharge




Fig. 8. Details of pumping plant model

sewers downstream from the pumping plant. River stages were set by piezometers located in the sewer lines at the same distance below the pumping plant as are the sewer outlets in the prototype. These sewer lines were later extended and tests made with the river stages reproduced in a tailbay at the end of the sewer discharge lines.

Original Design

33. Details of the original design of the pumping plant are shown on plate 3. Tests revealed the distribution of velocities in the intake




Fig. 9. View of pumping plant from north showing sump chamber in foreground and pump discharge channel in background. Water surface indicated is for conditions of pump flow




Fig. 10. Pumping plant from west showing pump discharge channel and sewer lines on riverward side of plant

transition to be uneven and losses in the outlet transition to be high for conditions of both pump and gravity flow. Plates 13 and 14 show the velocity distribution in the intake transition and the outfall lines for gravity and pump flow, respectively. Plate 15 indicates the velocity ranges at which the measurements were made. Losses in the discharge channel for the pumps also were very high because of the impediment to flow afforded by the cellular-type partition walls in the channel (figs. 9 and 10).

34. Pressure measurements throughout the intake and outlet

transitions for gravity and pump conditions are listed in tables 16-18 while table 19 lists the elevation of the water surface in the various compartments of the sump chamber and pump discharge channel.

Development of Revisions to Pumping Plant

Revised intake and outlet transitions

35. A revised transition (plate 16) was installed at the intake and the distribution of flow was improved slightly, especially for pumping conditions, as evidenced by the velocity patterns (plates 17-18). The outlet transition to the existing sewer was replaced by an elbow section (plate 16), which also improved flow conditions in the outlet area, Tables 16-19 show a comparison of the elevation of the hydraulic grade lines obtained in the sewer lines and in the pumping plant for both gravity and pump flow with the intake transition revised, and with both intake and outlet transitions revised. Plate 19 shows the locations of the piezometers. The gradient at the upper end of the intake transition was lowered a maximum of 3 ft by the revision of the intake and outlet transitions. Although the revised intake transition provided more even flow throughout, velocities were still higher in the right portion of the transition. However, the eddy which was present in the left portion of the intake transition for the original condition (plate 14) was eliminated. The tests also indicated that the upper part of the entrance to the outlet transition should be rounded and a bellmouthed entrance provided for the 72-in. sewer, as turbulent flow still existed in these areas.

Determination of sump operating range

36. It was desired to maintain the elevation of the hydraulic grade line at the upper end of the intake transition as near elev 416.4 as possible. During pumping operations this gradient was controlled by the water-surface elevation in the sump. Therefore, it was necessary to determine the maximum permissible water-surface elevation in the sump as well as the minimum elevation required to maintain full flow in the intake transition. This safe-operating range was determined to be between


elev 415.5 and 419.5 ft msl (plate 20). Maintenance of a sump elevation of 415.5 eliminated air from the intake transition. A sump elevation higher than 419.5 raised the elevation of the hydraulic grade line at the upstream end of the transition above the desired elevation of 416.4. Therefore, in order to maintain the 5-ft operating range as required for efficient operation of the sump pumps (paragraph 5), it will be necessary to lower the elevation of the sump and transition 1 ft, unless a different method of pump control can be used.


Tests of pump intakes

37. Tests were made to study the relative merits of the draft-tube type pump intake (fig. 11) and the open-pit type intake with separator walls (fig. 12 and plate 21). Visual observation made of the flow conditions existing in the sump chamber and intakes for both types indicated that flow in the open-pit intake was more turbulent than that in the draft-tube intake. However, the relative efficiency curves (plate 22) of the two intakes indicated the open-pit setting type of intake to be slightly more efficient than the draft-tube intake. It is believed that additional tests of the intakes should be made on a larger scale model with the prototype impeller and pump characteristics reproduced, as the scale of this model and the absence of individual pumps would tend to disparage the results obtained.

Operation of pumps

- 38. A study of the effects of operating various combinations of pumps was made with both the draft-tube and open-pit type intakes installed. In each series of tests the sump level was maintained between elev 417 and 422 and the outfall sewer was allowed to flow free (no river control). The first test consisted of starting the pumps in succession, beginning with the riverside pump and progressing toward the landside pump. The discharge of those pumps already operating did not change as additional pumps were started. No turbulence was observed in the sump until the next to last pump on the landside was started, at which time a marked increase in turbulence was noted in the sump. This turbulence was greatly increased when the most landward pump was started.
 - 39. When the order of starting the pumps was reversed, i.e., the








Fig. 12. Open-pit type pump intakes

pumps were turned on from the landside to the riverside, considerable turbulence was noted when the first pump was started and existed throughout the rest of the test. Numerous other combinations of pumps also were investigated and the effects noted. The starting of additional pumps had no effect on the capacity of the pumps already operating, regardless of the pumping combination used. The only effect noted for any test was the turbulence as discussed above. This turbulent condition is not believed sufficiently great to warrant revision of the design.

Enlargement of sluice gate

40. As the losses through the pumping plant for gravity flow were still slightly higher than considered desirable, one of the sluice gates between the lower end of the sump and the exit channel was enlarged (plate 23). The enlargement of the gate reduced the elevation of the water surface in the sump which in turn reduced the elevation of the hydraulic grade line at the upper end of the intake transition to elev 416.9 (table 20). The water-surface elevations in the sump and discharge

channel were also equalized (compartments 6, 14, and 15, table 21). No further revisions were made to lower the gradient for gravity flow, as representatives of the Louisville District stated that the gradient was satisfactory and any additional lowering desired could be obtained by streamlining the entrances to the outfall sewers.

Revisions to pump discharge channel

41. Several revisions were made to the pump discharge channel in order to increase its capacity. The first of these revisions consisted of removing the two baffle walls in the west exit channel and putting an ogee crest just below the step-down at the lower end of the south discharge channel (fig. 13). A 45-degree fillet, 2 ft on a side, was also added to the southwest corner of the pumping plant (plate 23). These revisions increased the maximum discharge capacity at high river stages from 575 cfs to 740 cfs and reduced the turbulence in the west discharge channel. Later tests indicated that the ogee section below the south channel was not required and it was removed from the model. The capacity of the discharge channel for high river stages was further increased to 920 cfs by cutting a 10-ft by 10-ft relief opening in the riverside of the southwest corner (fig. 14). The hydraulic grade line in the sewer below the pumping plant and the water-surface elevations in the discharge channel obtained during these tests are indicated in tables 22 and 23, respectively.

42. The required pump discharge of 1200 cfs with a river stage of 458.3 ft was not obtained by the preceding revision. The baffle walls in the south discharge channel still caused excessive losses. Therefore, that portion of the south wall baffle walls above elev 445.0 was removed. Although this revision increased the capacity of the discharge channel to the required amount, flow in this channel was still turbulent. Accordingly, all of the baffle walls were removed from the discharge channel and tests were made for various pump flows (table 24). Since supporting members were required in the discharge channel, however, twelve 2-ft-sq horizontal struts were installed. Tests made to determine the effect of these struts on flow conditions (table 25) revealed no obstruction to flow.




Fig. 13. View of baffle walls in pumping plant




Fig. 14. Relief opening in pump discharge channel

Baffle partition walls in sump chamber

43. In an attempt to reduce surges in the sump chamber, the baffle partition walls in the sump chamber were lowered from elev 420 to elev 415. Tests were made for both pump and gravity flow. These tests revealed no apparent improvement in flow conditions in the sump and no effect on the pressure readings formerly obtained (tables 26-27). The baffle partition walls were then completely removed and no change in sump action was noticed.

Sewer Line Riverward of Pumping Plant

- 44. The hydraulic grade lines for all flows during initial tests were maintained by a valve at the lower end of the model (plate 3), as only 45 ft (prototype) of the outfall sewers were reproduced below the pumping plant. An analysis was made of the losses* occurring in the outfall lines for both gravity and pump flow (tables 28-29) and of the computed hydraulic grade line elevation at the upper end of the outfall sewer as compared to that used in the model (table 30). These analyses indicated that the control elevations used during the model study for gravity flows of 1800 cfs and pump flows of 1200 cfs were fairly close to the computed elevations, although the elevation of the grade line used for pump flow of 1800 cfs was too low.
- 45. Accordingly, the outfall sewers were extended in accordance with plans furnished by the Louisville District (fig. 5) and a series of tests was made to determine the hydraulic grade lines for various operating conditions. The following data were obtained with the model conditions as indicated:
 - a. Hydraulic grade line existing in the 10-ft-7-in. by 10-ft-1/2-in. sewer without the pumping plant installed for a discharge of 1800 cfs and river stage elevations of 382.5 and 427.2 (plate 24).

^{*} Losses in miter bends determined from curve contained in "Energy Loss in Smooth- and Rough-Surfaced Bends and Curves in Pipe Lines," by Werner Schubait.

- b. Hydraulic grade lines existing in the sewer and through the pumping plant for gravity flow of 1800 cfs and river stages of 382.5, 412.0, and 427.2 (plate 25).
- c. Hydraulic grade lines in sewer for pump flows of 1800 and 1200 cfs at river stage elevations of 430 and 458.3, respectively (plate 26).

Velocities were measured for all the above flow conditions and the distribution of flow between the existing horseshoe-shaped sewer and the proposed 72-in. circular sewer was computed (table 31).

- 46. Negative pressures were measured in the sewer lines during some of the above tests, which indicated that the sewer lines had developed siphonic action. The model was revised by the addition of vents (fig. 5) and tests were made as indicated below. Hydraulic grade lines were determined for:
 - a. Existing conditions without the pumping plant, a flow of 1800 cfs and a river stage of 382.5. Vent installed in existing sewer at sta 0+00 (plates 24 and 27).*
 - b. Pumping plant installed with 1800-cfs gravity flow and river stage of 382.5. Vent installed in existing sewer at sta 0+00 and in 72-in. proposed sewer at sta 5+60 (plate 27).
 - c. Pumping plant installed with 1800-cfs gravity flow and a river stage of 382.5. Vents installed in existing sewer at sta 0+00, 5+40, and in 72-in. sewer at sta 5+60 (plate 28). Hydraulic grade lines were not obtained for river stages of 412.0 and 427.2 as the addition of air vents did not change the grade lines previously obtained without vents.

The above tests indicated that the outfall sewers should be vented to obtain the desired capacity for gravity flow. Velocity cross sections were taken in the outfall lines for the various flow conditions and the flow distribution (between the two outfall lines) was improved (table 31).

^{*} Station 0+00 located at piezometer 1, 247.34 ft upstream from pumping plant.

PART V: DISCUSSION OF TEST RESULTS

Surge Model

- 47. The simplified model of the Southern Outfall Sewer was constructed for the purpose of obtaining basic data regarding surge action to be expected in a sewer system embracing a main-line sewer and several laterals and risers. Initial studies were conducted to determine the water-hammer pressures encountered in a closed line and the amount of relief afforded these pressures by the addition of an open sump and risers. Additional studies made to determine the effect of varying the time of complete stoppage of pump discharge on the height of surge in the sump and risers indicated that within certain limits this variation in time made no appreciable difference in the height of surge produced.
- 48. The model tests also indicated that with the Southern Outfall Sewer as originally designed the possibility existed of large and destructive surges developing in the pumping plant sump and along the lower reaches of the main sewer. High or moderately high surges could develop under certain circumstances, not only from total shutdown of the pumping plant, but also from shutdown of individual pump units. Model tests indicated that the pumping plant itself could be protected from damage due to surges in the sump by installation of surge relief valves or flap gates that would open and allow discharge direct to the river. However, these features would not protect the area upline from the sump. Some reduction in surge upline from the sump appears possible by permitting overflow of risers (manholes) into storage areas constructed for the purpose. results of the time-of-concentration study of flow at the pumping plant from the various areas of the sewer system indicate that, if the sewer is under pressure as planned, a flow increase from any of the areas would be reflected in increased flow at the pumping plant almost immediately. The number of manholes tend to cause a slight time lag but not enough to be a serious factor in design considerations.
- 49. The results obtained from the model study have been compared with the results obtained from a method developed by the Ohio River

Division* for analytically determining the surge heights in a simple sewer system. The model and computed data compare favorably, thus permitting an analytical computation to be made of the surges to be expected in the Southern Outfall Sewer, rather than determining these surges from a more extensive model study.

Pumping Plant Model

- 50. Model tests of the State Fairgrounds Pumping Plant indicated that the original design did not produce the desired results. The intake and outlet transitions were revised in order to reduce flow losses through the pumping plant for gravity flow. The gate openings between the sump chamber and the pump discharge chamber were enlarged in order to lower the hydraulic grade line at the upper end of the intake transition to the desired elevation. The cellular construction of the pump discharge channel as originally designed restricted the flow during high river stages to such an extent that only approximately one-half the desired discharge could be passed at high river stages. The recommended design included the removal of all baffle walls in the pump discharge chamber to accommodate the desired discharge. In addition, a relief opening was recommended for direct passage of flow from the plant to the river during high river stages.
- 51. A study of the relative merits of the draft-tube and open-pit setting types of pump intakes indicated that the open-pit setting was slightly more desirable, although additional model tests are recommended before accepting these results as conclusive. Tests also indicated that the pumps could be operated in any desired combination without affecting the discharge of any other pumps in the plant. A series of tests made on the outfall lines indicated the desirability of venting these lines and of possibly increasing the size of the proposed 72-in. line to improve distribution of flow further.
 - 52. During the course of the tests, consideration was given to the

^{*} Appendices A and B.

location of the pumping plant immediately over the existing sewer alignment. This location should simplify intake transition problems; however, no tests were made with the plant in this position.

Table 1
WATER-HAMMER PRESSURES IN SEWER

Pumping Plant Omitted

Location	Discharge	Discharge = 1400 cfs		otype Pressure - Pounds Per Squar Discharge = 1800 cfs		Discharge = 2000 cfs	
	6-in. Tubing	Lower Section 4-in. Tubing	6-in. Tubing	Lower Section 4-in. Tubing	6-in. Tubing	Lower Section 4-in. Tubing	
Protection levee	356	1542	519	2000	565	2200	
*Pt 21 (4-in. Sect)	⁻	611				912	
Pt 21	307	512	393	685	456	736	
Pt 20	282	486	374	627	457	714	
Pt 19	288	544	390	695	465	771	
Pt 18	303	512	403	646	486	727	
Pt 17	290	551	437	690	454	742	

Notes: Time of valve closure = 0.944 seconds.

No laterals or risers.

All values are in prototype units except size of tubing.

^{*} This pressure cell added when lower end was changed to 4-in. tubing.

Table 2

EFFECT OF TIME OF VALVE CLOSURE ON WATER-SURFACE ELEVATIONS IN SUMP

No Surge Relief Openings

	= 1400 cfs fps in 4-in. Line		= 1800 cfs fps in 4-in. Line	-	= 2000 cfs fps in 4-in. Line
Time of Valve Closure Seconds	Max* Elev	Time of Valve Closure Seconds	Max* Elev	Time of Valve Closure Seconds	Max* Elev
0.94	468.30	0.94	485.90	0.94	495.20
3.96	468.48	6.79	485.60	5.66	497.28
10.19	468.38	19.24	485.60	33•96	496.80
39.05	468.32	47.54	485.12	57.17	496.64
78.11	467.42	81.50	484.48	93•39	495.52
109.24	467.20	96.22	484.16	156.22	494.88
135.84	466.40	136.41	483.20		

Notes: All values are in prototype units except size of sewer line.

Lower end of model constructed of 4-in. tubing.

^{*}Water-surface elevation in sump at 420.0 msl prior to beginning of tests.

Table 3

EFFECT OF RELIEF OPENINGS ON WATER-SURFACE ELEVATION IN SUMP

Discharge = 1	L400 cfs	Discharge =		Discharge = 2000 cfs Velocity = 22.35 fps in 4-in. Line		
Velocity = 15.89 fps	s in 4-in. Line	Velocity = 20.44 fp	s in 4-in. Line			
Time of		Time of	"	Time of		
Valve Closure	Max*	Valve Closure	Max*	Valve Closure	Max*	
Seconds	Elev	Seconds	Elev	Seconds	Elev	
2.8	453.8	2.8	455.7	4.5	457.0	
14.2	453.8	38.5	455•7	41.3	456.8	
33.4	453.8	65.1	455.7	106.4	456.6	
78.7	453.6	97.4	455•7	152.8	456.6	
118.9	453.6	133.6	455.4			

Notes: All values are in prototype units except size of sewer line. Lower end of model constructed of 4-in. tubing.

^{*}Water-surface elevation in sump at 420.0 ft msl prior to beginning of tests.

Table 4

EFFECT OF RELIEF OPENINGS AND PUMP OUTLETS

ON WATER-SURFACE ELEVATION IN SUMP

	= 1400 cfs fps in 4-in. Line	Discharge = 1 Velocity = 20.44 fps		Discharge - 2000 cfs Velocity = 22.35 fps in 4-in. Line		
Time of Valve Closure Seconds	Max* Elev	Time of Valve Closure Seconds	Max* Elev	Time of Valve Closure Seconds	Max* Elev	
2.8	444.5	4.0	451.2	4.0	452.2	
23.8	444.5	20.4	451.2	36.8	452.2	
54.9	444.2	49.8	450.9	52.1	452.2	
78.1	444.2	74.8	450.9	90.6	452.2	
125.1	443.2	121.7	450.9	140.4	451.8	
		134.1	450.7			

Notes: All values are in prototype units except size of sewer line. Lower end of model constructed of 4-in. tubing.

^{*}Water-surface elevation in sump at 420.0 ft msl prior to beginning of tests.

Table 5 EFFECT OF RISERS ON MAXIMUM SURGES IN SUMP AND SEWER LINE

		harge = :		Disc	harge =	levation msl 1800 cfs			2000 cfs
Condition	Elev	Upper Po	01 = 442.5	Elev Upper Pool = 455.0			Elev	Upper Po	01 = 465.0
and Location	Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds
Sump - No risers Sump	420.0	468.5	130	420.0	485.6	136	420.0	495.2	
Sump - 1 riser Sump Pt 21	420.0 433.9	469.0 463.5	132 127	420.0 441.1	485.3 479.0	136 136	420.0 446.1	495.4 488.7	141 139
Sump - 2 risers Sump Pt 21 Pt 19	420.0 433.8 436.6	469.0 463.9 455.7	130 127 127	420.0 441.1 444.8	485.1 479.5 470.1	136 130 133	420.0 446.3 451.8	494.9 488.8 479.4	141 133 130
Sump - 3 risers Sump Pt 21 Pt 19 Pt 17	420.0 433.6 436.5 439.6	468.8 463.5 456.0 448.5	133 133 133 133	420.0 441.3 445.8 450.3	485.3 479.3 470.3 462.0	136 138 136 136	420.0 446.1 451.6 457.5	495.8 488.8 479.7 470.6	140 140 140 141

Area of sump = 2100 sq ft. Area of risers = 50.68 sq ft each.

Time of valve closure approximately 3 seconds.

Table 6

MAXIMUM SURGES IN SUMP AND SEVER LINE

WITH 5 RISERS INSTALLED

						Elevation msl				
	Disc	harge =	1400 cfs	Disc	harge =	1800 cfs		Discharge = 2000 cfs		
4	Elev	Upper Po	ol = 436.5	Elev Upper Pool = 450.0			Elev	Upper Po	91 = 458.5	
	Normal	Max	Time of Rise	Normal	Max	Time of Rise	Normal	Max	Time of Rise	
Location	Elev	Elev	Seconds	Elev	<u>Elev</u>	Seconds	Elev	<u>Elev</u>	Seconds	
Sump	415.0	465.0	141	415.0	480.8	141.4	415.0	490.5	135.8	
Pt 21	429.0	459.5	147	435.8	474.0	135.8	441.3	483.5	135.8	
Pt 20	429.8	456.2	146.8	437.2	470.5	135.8	443.3	479.8	135.8	
Pt 19	432.1	452.5	146.9	440.8	466.0	135.8	447.0	475.3	135.8	
Pt 18	434.1	477.8	147	444.0	460.8	135.8	450.9	469.5	135.8	
Pt 17	435.5	445.3	147	445.8	458.3	135.8	453.5	467.0	135.8	

Area of sump = 2100 sq ft.

Area of each riser = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time valve is completely closed.

Table 7

MAXIMUM SURGES IN SUMP AND SEWER LINE

FOR PARTIAL REDUCTIONS OF FLOW

Initial Discharge 1800 cfs

					urface Ele d as Indic		
					500 - hp		1500-hp
		One	1500-	and	One	and	One
		hp	Pump	500 - h	p Pumps	_500-h	p Pumps
			Time of		Time of		Time of
	Normal	Max	Rise	Max	Rise	Max	Rise
Location	Elev	<u>Elev</u>	Seconds	<u>Elev</u>	Seconds	Elev	Seconds
Sump	420.0	432.8	141	441.1	130	461.6	130
Point 21	441.1	446.2	62	453.9	96	466.1	130
Point 19	445.4	448.1	62	450.4	96	456.8	130
Point 17	450.2	451.7	96	453.5	130	457.7	130
Point 17	450.2	451.7	96	453•5	130	457•7	

Notes: All values are in prototype units.

Sump and risers at points 17, 19, and 21 installed in model.

Area of sump = 2100 sq ft.

Area of risers = 50.68 sq ft each.

Discharge = 1800 cfs; elev upper pool = 455.0 ft msl.

Time of valve closure approximately 3 seconds.

Capacity of 1500-hp pump was 386 cfs. Capacity of 500-hp pump was 128 cfs.

Table 8

MAXIMUM SURGES IN SUMP AND SEWER LINE

Sump Area = 700 sq ft

	····	· · · · · · · · · · · · · · · · · ·				ce Elevation ms			
			1400 cfs o1 = 436.5		: 1800 cfs cool = 450.0		Discharge = 2000 cfs Elev Upper Pool = 458.5		
Location	Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds
Sump	415.0	490.0	74	415.0	514.5	76	415.0	527.5	79
Pt 21	429.0	478.0	79	436.0	498.9	82	441.3	512.0	82
Pt 20	429.5	473.5	85	438.2	493.5	85	443.0	505.0	88
Pt 19	432.0	464.5	85	441.0	483.5	85	447.0	494.3	88
Pt 18	434.0	456.2	88	777.0	472.6	90	450.3	482.7	89
Pt 17	435.0	451.5	91	445.9	467.5	94	453.0	476.7	90

Area of each riser = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time valve is completely closed.

Table 9

MAXIMUM SURGES IN SUMP AND SEWER LINE

Sump Area = 1400 Sq F

Discl									
		1400 cfs			1800 cfs		Discharge = 2000 cfs		
Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Seconds	Normal Elev	Max Elev	Time of Rise Seconds	
415.0	472.0	107	415.0	490.0	105	415.0	502.9	130	
429.6	462.8	96	436.0	480.2	96	441.3	492.2	130	
430.0	460.2	85	436.5	476.2	91	443.1	486.8	130	
432.0	455.5	88	441.0	470.5	88	447.0	480.5	130	
434.0	448.0	85	444.0	463.1	85	451.2	472.8	130	
435.0	446.0	85	445.8	460.0	85	453.6	469.5	130	
	Normal Elev 415.0 429.6 430.0 432.0 434.0	Normal Max Elev Elev 415.0 472.0 429.6 462.8 430.0 460.2 432.0 455.5 434.0 448.0	Elev Elev Seconds 415.0 472.0 107 429.6 462.8 96 430.0 460.2 85 432.0 455.5 88 434.0 448.0 85	Normal Max Time of Rise Normal Elev Elev Seconds Elev 415.0 472.0 107 415.0 429.6 462.8 96 436.0 430.0 460.2 85 436.5 432.0 455.5 88 441.0 434.0 448.0 85 444.0	Normal Max Time of Rise Normal Max Elev Elev Seconds Elev Elev 415.0 472.0 107 415.0 490.0 429.6 462.8 96 436.0 480.2 430.0 460.2 85 436.5 476.2 432.0 455.5 88 441.0 470.5 434.0 448.0 85 444.0 463.1	Normal Elev Max Elev Time of Rise Seconds Normal Elev Max Elev Time of Rise Seconds 415.0 472.0 107 415.0 490.0 105 429.6 462.8 96 436.0 480.2 96 430.0 460.2 85 436.5 476.2 91 432.0 455.5 88 441.0 470.5 88 434.0 448.0 85 444.0 463.1 85	Normal Max Time of Rise Elev Normal Elev Max Elev Time of Rise Elev Normal Elev 415.0 472.0 107 415.0 490.0 105 415.0 429.6 462.8 96 436.0 480.2 96 441.3 430.0 460.2 85 436.5 476.2 91 443.1 432.0 455.5 88 441.0 470.5 88 447.0 434.0 448.0 85 444.0 463.1 85 451.2	Normal Elev Max Elev Time of Rise Elev Normal Elev Max Elev El	

Area of each riser = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time valve is completely closed.

Table 10

MAXIMUM SURGES IN SUMP AND SEWER LINE

Sump Area = 2100 sq ft

				Water	-surface	Elevation msl		······································		
			1400 cfs	Discharge = 1800 cfs				Discharge = 2000 cfs		
	Elev	Upper Po	01 = 436.5	Elev	Upper Po	01 = 455.0		Upper Po	001 = 458.5	
	Normal	Max	Time of Rise	Normal	Max	Time of Rise	Normal	Max	Time of Ris	
Location	Elev	Elev	Seconds	<u>Elev</u>	Elev	Seconds	Elev	Elev	Seconds	
Sump	415.0	464.0	141	415.0	480.0	141	415.0	490.5	136	
Pt 21	429.0	459.0	147	435.8	474.0	136	441.3	483.5	136	
Pt 20	430.0	456.0	147	437.2	470.5	136	443.3	479.8	136	
Pt 19	432.0	452.0	147	440.8	466.0	136	447.0	475.3	136	
Pt 18	434.0	447.0	147	444.0	460.8	136	450.9	469.5	136	
Pt 17	435.0	445.0	147	445.8	458.3	136	453.5	467.0	136	

Area of each riser = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time valve is completely closed.

Table 11

MAXIMUM SURGES IN SUMP AND SEWER LINE

Pump Outlets and 60-in. Relief Openings Installed at Same Elevation

				Wat	ter-surf	ace Elevation ma	3l			
			1100 cfs			1400 cfs		Discharge = 1600 cfs		
	Elev	Upper Po	001 = 432.0	Elev (Jpper Po	001 = 436.5	Elev	Upper Po	001 = 442.5	
	Normal	Max	Time of Rise	Normal	Max	Time of Rise	Normal	Max	Time of Rise	
Location	Elev	Elev	Seconds	Elev	Elev	Seconds	Elev	Elev	Seconds	
Sump	415.0	438.0	96	415.0	452.5	91	415.0	453.0	85	
Pt 21	425.5	438.0	110	428.0	452.0	91	431.5	454.2	85	
Pt 20	426.0	441.0	141	429.2	450.0	91	432.5	452.8	85	
Pt 19	428.0	443.5	147	431.6	448.0	91	435.7	450.7	85	
Pt 18	429.0	444.0	192	433.0	445.0	124	437.8	448.0	88	
Pt 17	430.0	444.0	221	434.0	444.0	124	438.5	446.0	91	

Area of sump = 2100 sq ft.

Area of risers = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time the valve is completely closed.

Risers installed at points 17, 18, 19, 20, and 21.

All openings in sump at elevation 452.0 ft msl.

Table 12

EFFECT OF DISPERSION OF INFLOW ON MAXIMUM SURGES

IN SUMP AND SEWER LINE

	Lateral	Total	Water-surface Elevation msl Total Discharge at Sump = 1800 cfs Elev Upper Pool = 450.0						
Location	Inflow cfs	Normal Elev	Max Elev	Time of Rise Seconds					
Sump		415.0	480.0	142					
Pt 21	98	435.8	473.5	142					
Pt 20	24	437.5	469.5	142					
Pt 19	136	440.6	464.0	142					
Pt 18	64	444.0	459.0	142					
Pt 17	204	445.0	458.0	142					

Area of manhole = 50.68 sq ft.

Area of sump = 2100 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time the valve is completely closed.

Risers installed at points 17, 18, 19, 20, and 21.

A discharge of 1274 cfs introduced in main sewer upstream from Pt 17.

Table 13

EFFECT OF OVERTOPPING RISER AT POINT 21 ON

MAXIMUM SURGES IN SUMP AND SEWER LINE

						face Elevation				
	Elev To	op of Ri	ser = 440.0			s - Elev Upper Riser = 438.0		Elev Top of Riser = 436.0		
	Normal	Max	Time of Rise	Normal	Max	Time of Rise	Normal	Max	Time of Rise	
Location	<u>Elev</u>	Elev	Seconds	Elev	Elev	Seconds	Elev	<u>Elev</u>	Seconds	
Sump	415.0	462.6	113	415.0	461.8	113	415.0	461.3	116	
Pt 21	435.4			435.5			435.5			
Pt 20	437.2	455.3	141	437.2	455•5	141	437.2	455.5	158	
Pt 19	440.5	455.0	141	440.5	454.0	141	440.5	455.0	158	
Pt 18	443.8	453.0	141	443.8	453.0	141	443.8	453.0	158	
Pt 17	445.5	453.0	141	445.5	453.0	170	445.5	453.5	181	
			•							

Area of sump = 2100 sq ft. Area of risers = 50.68 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time the valve is completely closed.

Table 14

EFFECT OF OVERTOPPING RISER AT POINT 21 ON MAXIMUM SURGES IN SUMP AND SEWER LINE

Stoppage of One 1500-hp Pump (386 cfs)

		Dak			face Elevation		<u> </u>	
Elev To	op of Ri							er = 436.0
Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds	Normal Elev	Max Elev	Time of Rise Seconds
415.0	416.0	57	415.0	416.0	57	415.0	416.0	57
435•5	436.5	85	435.5	436.5	85	435.5		
437.2	438.2	113	437.2	438.2	113	437.2	438.0	68
440.5	441.5	141	440.5	441.5	141	440.5	441.0	96
443.8	444.5	141	443.8	444.5	141	443.8	443.8	- -
445.5	445.5		445.5	445.5		445.5	445.5	um das
	Normal Elev 415.0 435.5 437.2 440.5 443.8	Normal Max Elev Elev 415.0 416.0 435.5 436.5 437.2 438.2 440.5 441.5 443.8 444.5	Elev Top of Riser = 440.0 Normal Max Time of Rise Elev Elev Seconds 415.0 416.0 57 435.5 436.5 85 437.2 438.2 113 440.5 441.5 141 443.8 444.5 141	Elev Top of Riser = 440.0 Elev Top of Riser Normal Max Time of Rise Normal Elev Elev Seconds Elev 415.0 416.0 57 415.0 435.5 436.5 85 435.5 437.2 438.2 113 437.2 440.5 441.5 141 440.5 443.8 444.5 141 443.8	Elev Top of Riser = 440.0 Elev Top of Rise Normal Elev Top of Rise Normal Normal Max Time of Rise Elev Elev Normal Max Elev Elev 415.0 416.0 57 415.0 416.0 435.5 436.5 85 435.5 436.5 437.2 438.2 113 437.2 438.2 440.5 441.5 141 440.5 441.5 443.8 444.5 141 443.8 444.5	Elev Top of Riser = 440.0 Elev Top of Riser = 438.0 Normal Max Time of Rise Elev Elev Seconds 415.0 416.0 57 435.5 436.5 85 435.5 436.5 85 437.2 438.2 113 437.2 438.2 113 440.5 441.5 141 440.5 441.5 141 443.8 444.5 141 443.8 444.5 141	Elev Top of Riser = 440.0 Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Rise Normal Elev Top of Riser = 438.0 Idea of Riser = 438.0 <td>Elev Top of Riser = 440.0 Elev Top of Riser = 438.0 Normal Max Elev Elev Max Elev Top of Riser = 438.0 Normal Max Elev Elev Elev Top of Riser = 438.0 Normal Max Elev Elev Normal Max Elev Elev</td>	Elev Top of Riser = 440.0 Elev Top of Riser = 438.0 Normal Max Elev Elev Max Elev Top of Riser = 438.0 Normal Max Elev Elev Elev Top of Riser = 438.0 Normal Max Elev Elev Normal Max Elev Elev

Area of sump = 2100 sq ft

Area of risers = 50.68 sq ft

Time of partial valve closure approximately 1 second.

Time of rise measured from the time the valve movement is completely stopped.

 $\begin{array}{c} \underline{ \text{Table 15}} \\ \\ \text{MAXIMUM SURGES IN SUMP AND SEWER LINE} \end{array}$

Area of Risers = 201 sq ft

Discharge Elev Upper I mal Max ev Elev 5.0 463.9	Pool = 436.5 Time of Rise Seconds 141			1800 cfs 001 = 450.0 Time of Rise Seconds 153	Normal Elev 415.0	Upper Po Max Elev 489.0	2000 cfs 001 = 458.5 Time of Rise Seconds 164
mal Max ev Elev	Time of Rise Seconds	Normal Elev 415.0	Max Elev 479.9	Time of Rise Seconds 153	Normal Elev 415.0	Max Elev 489.0	Time of Rise Seconds
Elev 5.0 463.5	Seconds 141	Elev 415.0	Elev 479.9	Seconds 153	Elev 415.0	Elev 489.0	Seconds 164
463.5	5 141	415.0	479.9	153	415.0	489.0	164
				-	•	•	
458.0) 153	435.8	L72.5	1.50	1.1.0	1.02 -	~ 1
		37	T147	153	440.0	481.9	164
).0 456.1	153	437.6	470.9	158	442.0	479.5	170
2.0 452.2	164	440.6	466.3	170	446.0	474.1	175
5.0 448.0	164	444.0	461.7	170	449.5	468.7	181
5.5 446.0	170	445.8	459.1	170	452.0	466.2	181
;	.0 452.2	.0 452.2 164 .0 448.0 164	.0 452.2 164 440.6 .0 448.0 164 444.0	.0 452.2 164 440.6 466.3 .0 448.0 164 444.0 461.7	.0 452.2 164 440.6 466.3 170 .0 448.0 164 444.0 461.7 170	.0 452.2 164 440.6 466.3 170 446.0 .0 448.0 164 444.0 461.7 170 449.5	.0 452.2 164 440.6 466.3 170 446.0 474.1 .0 448.0 164 444.0 461.7 170 449.5 468.7

Notes: All values are in prototype units.

Area of sump = 2100 sq ft.

Time of valve closure approximately 1 second.

Time of rise measured from the time the valve is completely closed.

Table 16 ELEVATION OF HYDRAULIC GRADE LINE FOR GRAVITY FLOW CONDITIONS

Discharge = 1800 cfs Outlet Sewer Uncontrolled

Piez No.	Original Conditions	Revised Intake Transition	Revised Intake and Outlet Transitions
•	1.00.0	107.0	1
1 2 3 4 5 6 7 8	422.0	421.0	419.0
2	422.0	420.8	418.6
3	421.0	421.0	419.0
4	421.0	420.5	418.4
5	421.0	420.5	418.4
6	420.6	420.0	418.2
7	421.0	420.0	418.3
8	420.0	420.0	418.0
9	421.0	418.5	417.0
10	420.0	420.0	418.0
11	420.0	420.0	418.0
12	421.0	420.2	418.5
13	421.0	419.0	418.0
14	419.0	418.5	417.0
15	420.0	419.8	418.0
16	421.0	422.0	420.0
	421.0	422.0	
17	42L.0		420.0
18	421.0	422.0	420.0
19	421.0	422.0	420.0
20	421.0	422.0	420.0
21	422.0	422.5	420.4
22	422.0	420.5	420.5
23	422.0	422.0	420.4
24	422.0	422.5	420.4
25	423.0	422.8	421.0
34	422.0	422.5	421.0
35	422.0	422.5	421.0
49	423.0	423.0	421.4
50	407.0	407.0	408.5
51	398.6	399•5	400.5
52	398.6	399•5	400.0
53	410.0	409.0	410.0
54	409.0	409.0	409.5
55	409.0	408.0	409.0
56.	409.0	409.0	
			409.0
57 58	420.0	420.5	417.0
58 50	417.0	418.0	415.5
59	419.0	419.5	417.5
60	416.0	416.0	417.5
61	417.0	417.0	416.5
62	411.0	411.0	412.8
63	413.0	413.0	416.8
64	414.0	414.0	415.5
65 66	414.0	414.0	416.8
6 6	414.0	414.0	415.5
67 68	414.0	414.0	414.0
68	415.0	415.4	415.8
69	415.0	415.2	414.5
7 0	415.0	415.4	415.8
71	422.0	422.4	421.0
75	422.0	422.4	420.8
76	423.0	423.0	421.4
ריני דיני	423.0 423.0	423.0	421.4 421.4
77 78	423.0 423.0	423.0 423.0	421.4 421.4
10	423.0	#23.U	421.4

Note: Piezometer locations are shown on plate 19.

Discharge = 1800 cfs

River Stage = 430.0 ft msl

Piez	Original	Revised Intake	Revised Intake and
No.	Conditions	Transition	Outlet Transitions
1	420.0	418.5	418.5
2	419.4	418.4	418.4
2 3 4 5 6 7 8	419.8	418.5	418.5
ر ار	418.0	418.0	418.0
5	418.0	418.0	418.0
6	417.6	417.8	417.8
7	418.6	417.8	417.8
ģ	418.0	417.8	417.8
9	418.0	417.5	417.5
10	418.0	417.5	417.5
11	418.4	417.5	417.5
12	419.0	417.8	417.8
13	417.6	417.0	417.0
14	417.0	416.0	416.0
15	418.0	417.0	417.0
16	418.0	418.5	418.5
17	419.0	418.5	418.5
18	419.4	418.5	418.5
19	419.0	418.5	418.5
20	420.0	418.5	418.5
21	421.0	419.0	419.0
22	420.0	419.0	419.0
23	419.0	419.0	419.0
24 24	419.6	420.0	420.0
25	421.0	420.0	420.0
34	448.4	452.0	452.0
3 7	448.0	451.0	451.0
49	420.6	420.5	420.5
5 0	430.5	431.0	431.0
51	417 . 0	415.0	420.0
52	417.0	418.0	420.0
52	424.0	420.0	424.6
53 54	428.0	428.6	428.4
55	428.4	426.0	429.0
55 56	428.4	429.0	428 . 8
57	438.0	439.0	433.6
58	437.0	437.0	433.6
59	435.0	436.0	434.0
60	433.0	433.0	435.0
61	420.8	430.0	434.4
62	426.0	427.0	427.2
63	431.0	431.0	433.2
64	431.0	431.0	432.0
65	430.5	431.0	433.0
65 66	431.0	431.0	432.2
67	431.0	431.0	431.6
67 68	431.2	432.0	432.4
69	432.4	432.0	429.6
69 70	432.8	432.0	432.6
71	449.0	449.2	446.6
75	448.0	448.2	446.0
76	420.0	420.5	433.6
77	421.8	420.5	433.6
71 75 76 77 78	421.2	420.5	433.6
•.			

Note: Water-surface elevation in sump maintained at 420.0 ft msl at upper end. Piezometer locations are shown on plate 19.

Table 18

ELEVATION OF HYDRAULIC GRADE LINE FOR PUMP FLOW CONDITIONS

Discharge = 575 cfs* River Stage = 458.3 ft msl

		Discharge = 5/5 cis-	niver boage = 450.5 it msi						
Piez		Original	Revised Intake		Revised Intake and				
No.		Conditions	Transition		Outlet Transitions				
		420.2	419.0		419.6				
1			419.0		419.6				
2		417.6							
3 4		420.2	419.0		419.7				
4		420.1	419.0		419.8				
5		420.1	419.0		419.8				
5 6 7 8		420.0	419.0		419.8				
7		420.1	419.2		419.8				
8	•	420.0	419.2		419.8				
9		420.1	420.2		419.8				
10		420.1	419.2		419.8				
11		420.1	419.4		419.8				
12		420.2	419.6		419.9				
13		420.0	419.0		419.8				
14		419.8	419.4		419.6				
		420.0	419.8		419.8				
15				1					
16		420.1	420.2		420.0				
17		1	421.8		419.8				
1.8		420.2	420.4		420.0				
19		420.2	420.2		419.9				
20		420.2	420.2		420.0				
21		4 20. 2	420.8		420.0				
22		420.4	420.2		420.0				
23		420.4	420.2		420.0				
24		420.4	420.4		420.0				
25	-	420.4	420.4		420.0				
34		460.2	460.2		460.1				
25		460.1	460.1		460.0				
35 49		420.0	421.4		419.8				
50		458.2	458.0		458.5				
51		456.8	456.6		457.4				
5 2		456.8	456.6		457.3				
53		457.5	457.2		458.0				
54		458.0	457.6		458.3				
55		457•9	457.5		455.2				
56		458 . 0	457.6		458.4				
57		459.0	458.7		459.0				
58		458.8	458.5		453.0				
		458.7	458.4		459.0				
59 60		458.0	458.2		459.1				
61		457.7	457.8		457.6				
62		458.3	457.6		458.3				
		458 . 2	458.0		458.8				
63		470.2 hrs o	1,57.0		450.0				
64		458.2	457.9		458.7				
65 66		458.2	458.0	*	458.0				
66		458.1	458.0		458.6				
67		458.3	458.0		458.6				
67 68		458.2	458.0		458.6				
69		458.7	458.0		457.6				
70		458.3	458.0		456.6				
70 71		460.2	459.9	~ .	460.3				
75		460.0	459.8		460.0				
75 76			421.8		420.0				
ייניי ייניי			422.2		420.0				
77 78			422.2	44.	420.0				
10			766.6		720.0				

Notes: Water-surface elevation in sump maintained at 420.0 ft msl at upper end. Piezometer locations are shown on plate 19.

^{*} Maximum quantity of water that could be pumped due to piling up of water in upper end of discharge channel.

Table 19
WATER-SURFACE ELEVATIONS IN PUMPING PLANT

	Pumps Operating Discharge = 1800 cfs Tailwater = 430.0			Gravity Flow Discharge = 1800 cfs			Pumps Operating Discharge = 575 cfs Tailwater = 458.3		
Compartment No.	Original	Revised Intake	Revised Intake and Outlet	Original	Revised Intake	Revised Intake and Outlet	Original	Revised Intake	Revised Intake and Outlet
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	420.0 420.0 421.0 421.0 421.0 450.6 450.6 450.0 448.2 447.0 446.5 446.0 439.0 438.4	Same as Original	420.0 420.0 420.5 421.0 421.0 421.0 448.0 448.0 447.0 445.8 445.0 445.8 445.0 445.8 445.0	422.0 422.5 422.5 422.6 422.6 422.0	Same as Original	420.5 420.8 421.0 421.2 421.4 421.5	420.0 420.0 420.0 420.0 420.0 420.0 459.8 459.7 459.6 459.4 459.1 459.1 458.9 458.0	Same as Original	420.0 420.0 420.0 420.0 420.0 460.0 460.0 459.9 459.8 459.3 459.3 459.2 458.4

Notes: The water-surface elevations are average for each compartment.

For compartment locations see plate 15.

Table 20

EFFECT OF ENLARGED SLUICE GATE ON HYDRAULIC GRADE LINE

FOR GRAVITY FLOW CONDITIONS

Discharge = 1800 cfs River Stage Uncontrolled
Revised Intake and Outlet Transitions

No. Opening	Piez	Original Gate	Enlarged Gate
1			
2			
19.0 118.6 118.1 118.1 118.1 118.1 118.1 118.1 118.1 118.0 118.0 117.7 118.3 117.6 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 117.0 118.0 118.0 117.6 118.0 119.5 119.5 118.0 119.5 119.5 118.0 119.5 119.5 119.5 120.0 119.5 120.0 119.5 120.0 119.3 120.0 119.3 120.0 119.5 120.0 120.0 120.5 120.0 120.0 120.5 120.0	1		
5 418.4 418.0 6 418.3 417.7 7 418.3 417.8 8 418.0 417.0 10 418.0 417.0 11 418.0 416.9 12 418.0 417.6 13 418.0 416.9 14 417.0 416.1 15 418.0 416.9 16 420.0 419.5 17 420.0 419.5 18 420.0 419.5 19 420.0 419.3 20 420.0 419.3 21 420.0 419.3 22 420.0 420.1 22 420.1 420.1 22 420.2 420.2 23 420.1 420.2 24 420.1 420.2 25 421.0 420.5 35 421.0 420.5 49 421.4 420.0 402.5 400.5 400.5 49 421.0 40	2		418.4
5 418.4 418.0 6 418.3 417.7 7 418.3 417.8 8 418.0 417.0 10 418.0 417.0 11 418.0 416.9 12 418.0 417.6 13 418.0 416.9 14 417.0 416.1 15 418.0 416.9 16 420.0 419.5 17 420.0 419.5 18 420.0 419.5 19 420.0 419.3 20 420.0 419.3 21 420.0 419.3 22 420.0 420.1 22 420.1 420.1 22 420.2 420.2 23 420.1 420.2 24 420.1 420.2 25 421.0 420.5 35 421.0 420.5 49 421.4 420.0 402.5 400.5 400.5 49 421.0 40	3		
9	14		
9	5	418.4	418.0
9	6	418.2	
9	7	418.3	417.8
9	8	418.0	417.6
10	9	417.0	417.0
11	10	418.0	416.9
12	11	418.0	
13	12	418.5	
14 417.0 416.1 15 418.0 416.9 16 420.0 419.5 17 420.0 419.5 18 420.0 419.5 19 420.0 419.3 20 420.0 419.5 21 420.4 420.1 22 420.5 420.2 23 420.4 420.0 24 420.4 420.0 25 421.0 420.8 34 421.0 420.5 49 421.0 420.5 49 421.0 420.5 49 421.0 420.5 49 421.0 420.5 49 421.0 420.5 400.5 408.5 408.0 51 400.5 408.5 400.5 400.5 400.5 52 400.0 400.5 54 409.5 408.5 409.5 408.5 408.5 56 409.0 409.5 417.7 417.3	13	418.0	
15		417.0	
16 \$\delta 20.0\$ \$\delta 19.5\$ 17 \$\delta 20.0\$ \$\delta 19.5\$ 18 \$\delta 20.0\$ \$\delta 19.3\$ 20 \$\delta 20.0\$ \$\delta 19.5\$ 21 \$\delta 20.4\$ \$\delta 20.1\$ 22 \$\delta 20.4\$ \$\delta 20.0\$ 24 \$\delta 20.4\$ \$\delta 20.0\$ 25 \$\delta 21.0\$ \$\delta 20.5\$ 35 \$\delta 21.0\$ \$\delta 20.5\$ 42 \$\delta 20.5\$ \$\delta 20.5\$ 49 \$\delta 21.4\$ \$\delta 20.5\$ 49 \$\delta 21.0\$ \$\delta 20.5\$ 49 \$\delta 21.4\$ \$\delta 20.5\$ 49 \$\delta 21.4\$ \$\delta 20.5\$ 40 \$\delta 20.5\$ \$\delta 20.5\$ 40 \$\delta 20.5\$ \$\delta 20.5\$ 40 \$\delta 20.5\$ \$\delta 20.5\$ 42 \$\delta 20.0\$ \$\delta 20.5\$ 420.0 \$\delta 20.5\$ \$\delta 20.5\$ 420.0 \$\delta 20.5\$ \$\delta 20.5\$ 420.0 \$\delta 20.5\$ \$\delta 20.5\$ 400.1	15	418.0	416.9
17	16	420.0	
18 420.0 418.6 19 420.0 419.3 20 420.0 419.5 21 420.4 420.1 22 420.5 420.2 23 420.4 420.0 24 420.4 420.0 25 421.0 420.8 34 421.0 420.5 49 421.4 421.0 50 408.5 408.0 51 400.5 408.5 400.5 400.5 400.5 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 409.5 409.5 408.5 56 409.0 409.5 57 417.0 417.7 58 417.5 417.8 417.5 417.8 417.5 417.8 417.5 417.8 416.4 415.5 416.8 416.7 416.8 415.6 415.6 415.6 41		420.0	
19			418.6
\$\begin{align*} \begin{align*} \be		420.0	
21 420.4 420.2 22 420.5 420.2 23 420.4 420.0 24 420.0 420.8 34 421.0 420.5 35 421.0 420.5 49 421.4 421.0 50 408.5 408.0 51 400.5 400.5 52 400.0 400.5 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 408.5 57 417.0 417.7 58 417.5 416.4 59 417.5 417.3 60 417.5 417.3 61 416.5 416.4 412.8 412.5 63 416.8 416.7 64 415.5 416.8 416.8 415.6 65 416.8 415.5 66 415.5 416.6 67 414.0 413.7 <		420.0	419.5
22 \$\frac{1}{2}\text{.}\			420.1
23 24			420-2
2½ ½20.4 ½20.8 25 ½21.0 ½20.5 3½ ½21.0 ½20.5 ½9 ½21.4 ½21.0 50 ½68.5 ½68.0 51 ½00.5 ½00.5 52 ½00.0 ½00.1 53 ½10.0 ½09.5 54 ½09.5 ½08.5 55 ½09.0 ½09.5 57 ½17.0 ½17.7 58 ½17.5 ¼17.8 417.5 ¼17.8 ¼17.8 61 ¼16.5 ¼16.4 62 ¼12.8 ¼12.5 63 ¼16.8 ¼15.6 415.5 ¼15.6 ¼15.6 64 ¼15.5 ¼15.6 67 ¼14.0 ¼13.7 69 ¼14.5 ¼15.5			
25 421.0 420.5 34 421.0 420.5 49 421.4 421.0 50 408.5 408.0 51 400.5 400.5 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.8 61 416.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.3	5 1		420-0
34 421.0 420.5 35 421.0 420.5 49 421.4 421.0 50 408.5 408.0 51 400.5 400.5 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.8 61 416.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 415.7 68 415.8 415.3	25	421.0	420-8
35 421.0 420.5 49 421.4 421.0 50 408.5 408.0 51 400.5 400.5 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.4 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	<u> 3</u> μ	421-0	420.5
49 421.4 421.0 50 408.5 408.0 51 400.5 400.5 52 400.0 400.1 53 410.0 408.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 417.8 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	35		
50 408.5 408.0 51 400.5 400.5 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 412.5 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.5 415.3	Ĭ,		
51 400.5 400.1 52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	50		
52 400.0 400.1 53 410.0 409.5 54 409.5 408.5 55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	51	400.5	400.5
53 \$400.0 \$409.5 55 \$409.0 \$408.5 56 \$409.0 \$409.0 57 \$417.0 \$417.7 58 \$415.5 \$416.4 59 \$417.5 \$417.3 60 \$417.5 \$417.8 61 \$416.5 \$416.4 62 \$412.8 \$412.5 63 \$416.8 \$416.7 64 \$415.5 \$415.6 65 \$416.8 \$415.9 66 \$415.5 \$415.6 67 \$414.0 \$413.7 68 \$415.8 \$415.5 69 \$414.5 \$415.3	50	100 O	
55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	52 53	410.0	
55 409.0 408.5 56 409.0 409.0 57 417.0 417.7 58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	73 5h	li00 5	108.5
56 \$409.0 \$409.0 57 \$417.0 \$417.7 58 \$415.5 \$416.4 59 \$417.5 \$417.3 60 \$417.5 \$417.8 61 \$416.5 \$416.4 62 \$412.8 \$412.5 63 \$416.8 \$416.7 64 \$415.5 \$415.6 65 \$416.8 \$415.9 66 \$415.5 \$415.6 67 \$414.0 \$413.7 68 \$415.8 \$415.5 69 \$414.5 \$415.3	55	1100 U	108.5
57 \$17.0 \$17.7 58 \$415.5 \$416.4 59 \$417.5 \$417.3 60 \$417.5 \$417.8 61 \$46.5 \$416.4 62 \$412.8 \$412.5 63 \$416.8 \$416.7 64 \$415.5 \$415.6 65 \$416.8 \$415.9 66 \$415.5 \$415.6 67 \$414.0 \$413.7 68 \$415.8 \$415.5 69 \$414.5 \$415.3	56		100.0
58 415.5 416.4 59 417.5 417.3 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	57		
59 417.5 417.8 60 417.5 417.8 61 416.5 416.4 62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	ノi 58	h15 5	1.76 1
60 \$\\ 417.5\$ \$\\ 416.4\$ 61 \$\\ 416.5\$ \$\\ 416.4\$ 62 \$\\ 412.8\$ \$\\ 412.5\$ 63 \$\\ 416.8\$ \$\\ 415.6\$ 64 \$\\ 415.5\$ \$\\ 415.6\$ 65 \$\\ 416.8\$ \$\\ 415.9\$ 66 \$\\ 415.5\$ \$\\ 415.6\$ 67 \$\\ 414.0\$ \$\\ 413.7\$ 68 \$\\ 415.8\$ \$\\ 415.5\$ 69 \$\\ 414.5\$ \$\\ 415.3\$	50 50	h17.5	
61	60	117 E	
62 412.8 412.5 63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	61	1165	41(.0
63 416.8 416.7 64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	60	1:10.9	120.5
64 415.5 415.6 65 416.8 415.9 66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	62.		サエ と。 フ 1・1 6 97
66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	63 6):	har r	410. (
66 415.5 415.6 67 414.0 413.7 68 415.8 415.5 69 414.5 415.3	6E	+±2•2 h16 Ω	,4±7.•0
67 414.0 413.7 68 415.8 415.5 69 414.5 415.3 70 415.8 415.5 71 421.0 420.5	66	7.7 = - 7.7 = -	417.7 has 6
68 415.8 415.5 69 414.5 415.3 70 415.8 415.5 71 421.0 420.5	00 69	サエフ・フ hah	
69 415.5 70 415.8 415.5 71 421.0 420.5	0 (20	414.U	413.7
70 415.8 415.5 71 421.0 420.5	60		415.5 12.6
71 415.5 421.0 420.5	99	414.5 ham 0	415.3
(1 421.0 420.5	in In	41).0	415.5
	(T	421.0	420.5

Note: Piezometer locations are shown on plate 19.

Table 21 EFFECT OF ENLARGED SLUICE GATE ON WATER-SURFACE ELEVATIONS FOR GRAVITY FLOW CONDITIONS

Discharge = 1800 cfs River Stage Uncontrolled

Revised Intake and Outlet Transitions

Compartment No.	Original Gate Opening	Enlarged Gate Opening
1	420.5	420.0
2	420.8	420.4
3	421.0	420.6
4	421.2	420.7
5	421.4	420.9
6	421.5	421.0
14	421.0	421.0
15	420.0	420.0

Notes: The water-surface elevations are average for each compartment. For compartment location see plate 15.

Table 22

EFFECT OF REVISIONS TO PUMP DISCHARGE CHANNEL ON HYDRAULIC GRADE LINE

Revised Intake and Outlet Transitions

Piez No.	Discharge = 1800 cfs River Stage = 430.0 ft msl Modified Step West Baffles Removed	Discharge = 740 cfs River Stage = 458.3 ft msl Modified Step West Baffles Removed	Discharge = 920 cfs River Stage = 458.3 ft msl Modified Step West Baffles Removed Relief Opening Installed
50 51 52 53 54 55 56	428.0 421.0 421.0 428.3 428.5 428.9 429.5 436.2	458.0 456.7 456.8 457.9 458.0 457.8 457.9	458.4 457.1 457.0 458.1 458.0 458.1
57 58 59 60 61 62 63	436.2 436.1 434.6 436.0 434.0 428.2 433.6	459.0 459.0 458.9 459.1 458.9 457.8 458.8	459.0 458.9 458.8 459.0 459.3 458.1 458.8
64 65 66 67 68 69	432.8 433.2 432.9 431.4 432.8 432.6 432.8	458.5 458.7 458.6 458.4 458.5 458.5	458.6 458.6 458.6 458.4 458.6 458.6

Note: Locations of piezometers are shown on plate 19.

Table 23

EFFECT OF REVISIONS TO PUMP DISCHARGE CHANNEL ON

WATER-SURFACE ELEVATIONS IN PUMPING PLANT

Revised Intake and Outlet Transitions

Compartment No.	Discharge = 1800 cfs River Stage = 430.0 ft msl Modified Step West Baffles Removed	Discharge = 740 cfs River Stage = 458.3 ft msl Modified Step West Baffles Removed	Discharge = 920 cfs River Stage = 458.3 ft msl Modified Step West Baffles Removed Relief Opening Installed
1	420.0	420.0	420.0
2	420.0	420.0	420.0
3	420.0	420.0	420.0
4	420.0	420.0	420.0
5	420.0	420.0	420.0
6	420.0	420.0	420.0
7	442.9	460.0	460.0
- 8	442.6	459.8	459•9
9	441.8	459•7	459.8
10	440.3	459•4	459.4
11	439.6	459•2	459.3
12	438 . 7	459.0	459.1
13	438.0	458.8	458.6
14	438.0	458.2	458.6
15	437.8	458.0	458.5

Note: Locations of compartments are shown on plate 15.

ON WATER-SURFACE ELEVATIONS IN PUMPING PLANT

Revised Intake and Outlet Transitions

	Sout	h Baffles Re	moved to Ele	v 445.0	South	Baffles Co	mpletely Rem	oved
~ .	Relief Ope	ning Closed	Relief Open:	ing Operating	Relief Open		Relief Open	ing Operating
Compart-	0 1000	Q = 925	0 7000	Q = 1350	0 1900	Q = 1050	0 7000	Q = 1670
ment	Q = 1800	(max)	Q = 1200	(max)	Q = 1800	(max)	Q = 1200	(max)
No.	RS = 430.0	RS = 458.3	RS = 458.3	RS = 458.3	RS = 430.0	RS = 450.3	RS = 458.3	RS = 458.3
1	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
2	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
3	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
4	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
5	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
6	420.0	420.0	420.0	420.0	420.0	420.0	420.0	420.0
7	444.0	459.2	459.2	459.4	440.1	459.3	459.0	459.8
8	443.4	459.2	459.2	459•4	439•7	459•3	459.0	459•7
9	442.7	459.1	459.1	459.3	439.6	459.5	458.9	459.6
10	441.6	459.0	458.8	458.9	439.1	459.2	458 . 8	459.5
11	439.0	458.8	458.6	458.6	437.6	459.1	458.7	459.耳
12	438.5	458.7	458.4	458.4	437.4	459.0	458.6	459.2
13	438.0	458.5	458.4	458.4	437.1	459.0	458.6	459.0
14	437.8	458.5	458.3	458.3	436.5	458.9	458.6	459.1
15	437.5	458.5	458.4	458.3	437.6	459.1	458.8	459.2
						·		

Notes: Locations of compartments are shown on plate 15. All elevations in ft msl.

Table 25

WATER-SURFACE ELEVATIONS IN PUMPING PLANT WITH STRUTS

IN SOUTH CHANNEL REPLACING BAFFLE WALLS

Revised Intake and Outlet Transition

Compartment No.	Discharge = 1200 cfs River Stage = 458.3 ft ms1	Discharge = 1800 cfs River Stage = 430.0 ft msl
1	420.0	420.0
2	420.0	420.0
3	420.0	420.0
3 4	420.0	420.0
5	420.0	420.0
5 6	420.0	420.0
	459.2	440.7
7 8 9	459.2	440.0
9	459.1	439•7
1.0	459.0	439.5
11	458.9	438.0
12	458.7	437.7
13	458.5	437.3
14	458.7	436.3
15	458.7	437.9
		3, ,

Notes: Locations of compartments are shown on plate 15.

Spillway crest removed from south channel stepdown.

Fillet still in southwest corner.

Table 26

EFFECT OF REMOVAL OF BAFFLE WALLS FROM SUMP CHAMBER

ON WATER-SURFACE ELEVATIONS IN PUMPING PLANT FOR GRAVITY FLOW

Enlarged Gate Opening
Revised Intake and Outlet Transitions

	Discharge :	= 1800 cfs	······································	
Compartment	Bottom of Sump Baffles	Bottom of Sump Baffles at Elev 415.0		
No.	at Elev 420.0	East*	West*	
1	420.0	420.0	420.0	
2	420.5	420.0	420.5	
3	420.6	420.2	420.8	
14	420.8	420.5	421.0	
5	420.9	420.5	420.5	
6	421.0	420.4	420.4	
14	420.2	420.0	420.0	
15	420.2	420.0	420.0	

^{*}Denotes average water-surface elevation measured along east and west sides, respectively, of each compartment.

Note: Locations of compartments are shown on plate 15.

Table 27

EFFECT OF REMOVAL OF BAFFLE WALLS FROM SUMP CHAMBER

ON ELEVATION OF HYDRAULIC GRADE LINE FOR GRAVITY FLOW CONDITIONS

Enlarged Gate Opening Revised Intake and Outlet Transitions

Piez		T) a ± ± a ===			
			of Sump Baffles	Bot	tom of Sump Baffle
No.		at	Elev 415.0		at Elev 420.0
1			418.5		418.6
2			418.0		418.3
			418.1		418.6
3					418.1
4			417.5		
Ž			417.3		418.0
6			417.1		417.4
3 4 5 6 7 8			417.3		417.9
					417.5
9			416.8		417.0
10			416.6		417.0
11			417.1		417.3
12			417.1		4 17. 5
13			416.9		416.8
14			416.0		416.1
15			416.9		417.0
<u>16</u>			418.8		419.4
17			419.0		419.5
18			419.3		419.5
			419.0		419.4
19			419.0		419.5
20			418.9		
21			419.8		420.0
22			419.9		420.0
23			419.9		420.2
24			420.0		420.0
25			420.2		420.3
49			420.2		420.8
50			407.7		408.0
51			400.0		400.5
52			400.0		400.1
53			410.0		409.5
54			409.0		408.5
55			408.4		408.5
56			408.9		409.0
			417.6		417.7
57			416.4		416.4
58					417.3
59			417.1		47(•2
60			418.1		418.2
61			416.7		416.4
62			412.5		412.5
63 64			416.7		416.7
64		÷ .	415.6		415.6
65 66	,		416.0		415.4
66			415.6		415.6
67 6 8			413.9		413.7
6 <u>8</u>		•	415.6		415.5
69			415.5		415.3
					·
70			415.7		415.5

Note: Location of piezometers shown on plate 19.

Table 28

COMPUTED FLOW LOSSES IN PROTOTYPE OUTFALL SEWER LINES - SUMP TO EXIT DISTRIBUTION OF FLOW COMPUTED FROM VELOCITY MEASUREMENTS

GRAVITY FLOW

Sewer	Discharge cfs	Section	Area in Sq ft	Head Loss in Pipe	Entrance Loss K = 0.5	Contraction Loss	Enlargement Loss	Bend Loss #1 #2	Exit Loss	Total Loss
Existing n = 0.16	1200 Total Q = 1800 cfs	A B C	88.6 49.3 54.3	0.88 3.14 0.98	1.43	0.88	0.81	0.46 0.46	7.62	2.31 5.75 8.60 16.66
Proposed 72 in. n = .013	600 Total Q = 1800 cfs	A B C	28.3 28.3 28.3	2.95 1.97 0.89	3.48			0.35 0.35	6.96	6.43 2.67 7.85 16.95
Existing n = .016	356 Total Q = 1200 cfs RS = 458.3	A B C	88.6 49.3 54.3	0.08 0.28 0.09	0.08	0.06	0.07	0.04 0.04	0.67	0.16 0.49 0.76 1.41
Proposed 72 in. n = .013	179 Total Q = 1200 cfs RS = 458.3	A B C	28.3 28.3 28.3	0.26 0.18 0.08	0.21			0.06	0.62	0.47 0.24 0.70 1.41

Notes: Distribution for flow of 1200 cfs determined as follows: Total flow (1200) less flow through relief opening (665) = flow through sewers (535). This flow was distributed between existing sewer and proposed sewer in same ratio as for gravity flow at 1800 cfs.

The 72-in. sewer assumed to have same slope as existing sewer and a constant area. Pipe assumed flowing full.

Table 29

COMPUTED FLOW LOSSES IN PROTOTYPE OUTFALL SEWER LINES - SUMP TO EXIT

DISTRIBUTION OF FLOW COMPUTED FROM VELOCITY MEASUREMENTS

PUMP FLOW

Sewer	Discharge cfs	Section	Area in Sq ft	Head Loss in Pipe	Entrance Loss K = 0.5	Contraction Loss	Enlargement Loss	Bend Loss #1 #2	Exit Loss	Total Loss
Existing n = .016	1360 Total Q = 1800 cfs	A B C	88.6 49.3 54.3	1.13 4.04 1.25	1.29	1.73	1.05	0.59 0.59	9.76	2.42 8.00 11.01 21.43
Proposed 72 in. n = .013	440 Total Q = 1800 cfs	A B C	28.3 28.3 28.3	2.42 1.61 0.73	1.32			0.19 0.19	3.76	3.74 1.99 4.49 10.22
Existing n = .016	405 Total Q = 1200 cfs	A B C	88.6 49.3 54.3	0.10 0.36 0.11	0.11	0.12	0.10	0.055 0.055	0.87	0.21 0.69 0.98 1.88
Proposed 72 in. n = .013	130 Total Q = 1200 cfs	A B C	28.3 28.3 28.3	0.21 0.14 0.06	0.11			0.015 0.015	0.33	0.32 0.17 0.39 0.88

Notes: Distribution for flow of 1200 cfs determined as follows: Total flow (1200) less flow through relief opening (665) = flow through sewers (535). This flow was distributed between existing sewer and 72-in. sewer in same ratio as for pump flow at 1800 cfs.

The 72-in. sewer assumed to have same slope as existing sewer and a constant area. Pipe assumed flowing full.

Table 30

ELEVATION OF HYDRAULIC GRADE LINE AT

UPPER END OF OUTFALL LINES

Location	Model Elev msl	Computed Elev msl Dist A	Computed Elev msl Dist B	
		Gravity Flow - 1800 cfs		
Exist. Sewer Piez. 70	415.5	413.2		
72-in. Sewer Piez. 56	409.0	408.6		
		Pump Flow - 1800 cfs		
Exist. Sewer Piez. 70	432.3	442.1	446.2	
72-in. Sewer Piez 56	428.2	436.0	434.8	
		Pump Flow - 1200 cfs		
Exist. Sewer Piez. 70	458.5	459.2	459.7	
72-in. Sewer Piez. 56	458.0	458.9	458.7	

Note: Elev at piezometer 70 is average of piezometers 68 and 70. Elev at piezometer 56 is average of piezometers 54, 55, and 56. Distribution A is the distribution of flow as indicated in table 28.

Distribution B is the distribution of flow as indicated in table 29.

All measurements are in prototype units.

Table 31

DISTRIBUTION OF FLOW BETWEEN EXISTING SEWER


AND PROPOSED 72-IN. SEWER


	·	Discharg	e in cfs		
	Not	Vented		Vented	
Test Condition	Large Sewer	72-in. Sewer	Large Sewer	72-in. Sewer	
Gravity Flow Total Q = 1800 RS = 382.5	975	825	1170	630	
Gravity Flow Total Q = 1800 RS = 412.0	1220	580	1229	580	
Gravity Flow Total Q = 1800 RS = 427.2	1250	550	1230	570	
Pump Flow Total Q = 1800 RS = 430.0	1360	440	1260	540	
Pump Flow Total Q = 1200* RS = 458.3	310	110	310	110	


^{*} Excess flow carried by overflow relief opening.


Notes: All discharges in prototype cfs.

All elevations in ft msl.











RECORDING OF CALIBRATION OF PRESSURE CELL




NOTE: LINES ABOVE BASELINE INDICATE NORMAL OPERATING PRESSURE. LINES BELOW BASELINE INDICATE BELOW NORMAL OPERATING PRESSURES.

OSCILLOGRAPH RECORDING FOR CLOSURE OF VALVE

TYPICAL OSCILLOGRAPHS
FOR
MEASUREMENT OF PRESSURES






NOTE:


VELOCITY 6.96 FT PER SEC.
TIME OF VALVE CLOSURE 0.944 SEC.
MODEL CONSTRUCTED OF 6-IN. TUBING
THROUGHOUT.
NO LATERALS OR RISERS.
ALL VALUES GIVEN IN PROTOTYPE UNITS.

PRESSURE WAVES FOR SUDDEN CLOSURE OF VALVE 6-INCH TUBING DISCHARGE 1400 CFS




VELOCITY 8.93 FT PER SEC.
TIME OF VALVE CLOSURE 0.944 SEC.
MODEL CONSTRUCTED OF 6-IN TUBING
THROUGHOUT.
NO LATERALS OR RISERS.
ALL VALUES GIVEN IN PROTOTYPE UNITS.

PRESSURE WAVES FOR SUDDEN
CLOSURE OF VALVE
6-INCH TUBING
DISCHARGE 1800 CFS



VELOCITY 9.93 FT PER SEC.
TIME OF VALVE CLOSURE 0.944 SEC.
MODEL CONSTRUCTED OF 6-IN. TUBING
THROUGHOUT.
NO LATERALS OR RISERS.
ALL VALUES GIVEN IN PROTOTYPE UNITS.


PRESSURE WAVES FOR SUDDEN CLOSURE OF VALVE 6-INCH TUBING DISCHARGE 2000 CFS



VELOCITY IN 6-IN. SECTION 6.96 FT PER SEC. VELOCITY IN 4-IN. SECTION 15.67 FT PER SEC. TIME OF VALVE CLOSURE 0.944 SEC. MODEL CONSTRUCTED OF 4-IN. AND 6-IN. TUBING. NO LATERALS OR RISERS.

NO LATERALS OR RISERS.
ALL VALUES GIVEN IN PROTOTYPE UNITS.


PRESSURE WAVES FOR SUDDEN CLOSURE OF VALVE LOWER SECTION OF 4-INCH TUBING DISCHARGE 1400 CFS



VELOCITY IN 6-IN. SECTION 8.93 FT PER SEC. VELOCITY IN 4-IN. SECTION 20.09 FT PER SEC. TIME OF VALVE CLOSURE 0.944 SEC. MODEL CONSTRUCTED OF 4-IN. AND 6-IN. TUBING. NO LATERALS OR RISERS.

NO LATERALS OR RISERS.
ALL VALUES GIVEN IN PROTOTYPE UNITS.


PRESSURE WAVES FOR SUDDEN CLOSURE OF VALVE
LOWER SECTION OF 4-INCH TUBING DISCHARGE 1800 CFS





VELOCITY IN 6-IN. SECTION 9.93 FT PER SEC. VELOCITY IN 4-IN. SECTION 22.35 FT PER SEC. TIME OF VALVE CLOSURE 0.944 SEC. MODEL CONSTRUCTED OF 4-IN. AND 6-IN. TUBING. NO LATERALS OR RISERS.


ALL VALUES GIVEN IN PROTOTYPE UNITS.

PRESSURE WAVES FOR SUDDEN CLOSURE OF VALVE LOWER SECTION OF 4-INCH TUBING DISCHARGE 2000 CFS










NOTE: COMPARTMENT NUMBERS ARE FOR ORIGINAL AND REVISED CONDITIONS


PITOT TUBE LOCATIONS ARE FOR ORIGINAL AND REVISED INTAKE AND OUTLET TRANSITIONS

ALL VALUES ARE IN PROTOTYPE UNITS

PITOT TUBE VERTICALLY MOUNTED

COMPARTMENT NUMBERS
AND
PITOT TUBE LOCATIONS






ELEV. 412.12

ELEV. 410.52

ELEY. 408.92

ELEV. 407.32

ELEV. 406.68



0 6.0 6.4 7.2


0 3.9 5.1 6.4 7.2 9.1 10.2 12.0 14.4 15.4 15.7

0 5.1 6.4 6.0 9.1 10.6 14.0 16.0 16.4 16.4

0 3.2 6.0 6.8 9.4 10.6 14.0 15.7 16.4

0 0 5.1 7.9 8.5 12.2 14.4 16.0 17.3

0 0 0 3.9 6.8 6.8 12.4 14.4 14.0



9.4 10.6 12.0 11.6

ELEV. 414.0

ELEV. 412.0

ELEV. 410.0

ELEV. 408.0 ELEV. 406.0

ELEV. 404.0

LEEV. 403.5

INLET SEWER LINE

23,4

22.7

22.0

20.8

18.2

.


INVERT ELEV 405.28

NOTE: ALL MEASUREMENTS ARE IN THEIR PROTOTYPE EQUIVALENTS.

TEST CONDITIONS

DISCHARGE 1800 CFS SUMP ELEV 420.0


VELOCITY CROSS SECTIONS
REVISED INTAKE AND OUTLET
GRAVITY FLOW




DISCHARGE 1800 CFS SUMP ELEV 420.0 RIVER STAGE 430.0

VELOCITY CROSS SECTIONS

REVISED INTAKE AND OUTLET
PUMP FLOW







NOTE: DISCHARGE 1800 CFS.
ALL PUMPS OPERATING.

EFFECT OF SUMP ELEVATION ON HYDRAULIC GRADE LINE AT ENTRANCE TO PUMPING PLANT









NOTE: ALL UNITS ARE IN THEIR PROTOTYPE EQUIVALENTS.


DETAILS OF PUMP INTAKES


SCALE













DISCHARGE 1800 CFS

NOT VENTED

NOTE: INITIAL CONDITIONS DENOTE PUMPING PLANT INSTALLED.

HYDRAULIC GRADE LINES
INITIAL CONDITIONS
GRAVITY FLOW






TEST CONDITIONS

DISCHARGE 1800 CFS RIVER STAGE 382.5

NOTE: STATION 0+00LOCATED 247.34 FT UPSTREAM FROM PROPOSED PUMPING PLANT.

HYDRAULIC GRADE LINES

INITIAL CONDITION VS NOT VENTED EXISTING CONDITION GRAVITY FLOW



APPENDIX A

DEVELOPMENT OF ANALYTICAL METHOD FOR DETERMINATION OF SURGES IN SEWERS by R. L. Irwin*


- 1. A search of the available files pertaining to engineering literature, published both in the United States and in foreign countries, indicated that a satisfactory method for the solution of the surge problem in the Southern Outfall Sewer was not to be found. Numerous articles and papers pertaining to surges in penstocks in power systems were available; however, for the condition of multiple risers and laterals, apparently the only solution depended upon the use of model studies. Accordingly, the simplified undistorted 1:32-scale model, described in the basic report, was authorized. To reduce costs to a minimum only about 10,000 ft of the prototype sewer was reproduced. Risers were added at intervals in the main sewer line to simulate the effect of manholes.
- 2. Simultaneously, a study was made of the possibility of developing a procedure for computing the height of surge rise to be expected at various locations. One of these computations related to the features in the model, and the results compared very favorably with results of the model tests conducted at the Waterways Experiment Station. The method later was described to personnel of the Louisville District Office, who continued the computations and took into consideration the characteristics of flow found in the prototype sewer rather than those used in the model. An explanation of the computations made in the Louisville District is found in appendix B of this report.
- 3. The computational procedure consists in the derivation and solution of a set of simultaneous equations. In deriving a set of equations for solution, the number of unknown quantities are dependent upon the number of sections of pipe between the pools and surge tanks. It is

^{*} Formerly of the Ohio River Division and now with the Washington District.

necessary to obtain the results for small successive finite increments of time, assuming the discharge, friction head, velocity head, elevation, and retarding head to vary as a straight line during the interval of time involved. The variable factors are adjusted after each step before proceeding with the computation for determining the next series of incremental changes. On plate Al is shown the derivation of the basic equations used for determining the set of simultaneous equations applying to a continuous sewer with numerous risers or surge tanks. It is necessary that either the elevation of the uppermost pool remain constant, or that flow into the pool and the dimension of the pool be given or assumed. The derivation may be expanded to include as many laterals as are desirable, provided that each junction of the lateral with the main sewer or another lateral is made at a riser or surge tank. The uppermost point in each lateral system also must meet the conditions stated for the uppermost point on the main sewer. The finite increment of time should not be taken too large or the computation must be carried to too many places to obtain a check. The results obtained through use of time increments that are quite large often lead to serious errors because of the approximations used in deriving the basic equation.

- 4. If it should be desirable that the relationship for friction head and velocity head follow approximately a curve line, it then becomes necessary to solve a new set of simultaneous equations for each step. A change in the area of the riser for change in elevation also would require a separate solution of equations for each step. In many instances the same solution of equations can be used for several steps, as demonstrated by the computations on plate A2.
- 5. The computations shown on plate A2 were made for conditions similar to those used in the model tests, and hydrographs which are plotted from the results of the computation are shown on plate A3. The results of the model tests plotted to the same scale as used to plot the computed results are shown on plate A4.
- 6. From a comparison of the model and computational hydrographs the proposed computational procedure appears to be quite satisfactory. It, therefore, was considered expedient and economical to terminate the

model studies and complete the study through the computational procedure outlined above.



(Diagram represents surges during a short time interval in two downstream tanks of a multiple tank system with constant outflow (Q_0) from system and no direct inflow into downstream tank. Thus interval represented is a short time after beginning of surge action as \mathbb{Z}_1 would be equal to \mathbb{P}_1 at instant surge action begins.)

- Q Discharge in section of sewer upstress from tank at beginning of time period considered (cfs).
 I Uniform tributary inflow considered to enter surge tank directly (cfs).
 Retardation (or acceleration) in discharge in section of sewer during time period considered (cfs).
 A Cross-sectional area of surge tank (ag ft).
 a Cross-sectional area of surge tank (ag ft).
 b Length of sewer section (ag ft).
 L Length of sewer section (ag ft).
 E Blevation of water surface in surge tank at beginning of time period considered (ft).
 P Hisse (or fall) in water surface in tank during time period considered (ft).
 P Percentric level of tank at beginning of time period considered (ft).
 P Pydramitr (level of tank at beginning of time period considered (ft).
 P Pydramitr (losses in section of sewer for initial conditions.)
 P Pydramit (losses in section of sewer for initial conditions (ft).
 AF Change in hydraulic losses in reach during time period considered (ft).
 C Rydramic loss factor such that Cg + AF . (fo simplify computations it has been assumed that hydramic losses are linear functions of sewer discharge.)
 h Retarding (or accelerating) head acting to cause retardation (or acceleration due to gravity (32.2 ft/sec²).

- 0, 1, 2, ... n Tank number or sewer section.

 b Beginning of time period.

 a Average during time period.

 End of time period.

DERIVATION OF BASIC EQUATIONS

From the laws of action it can be shown that, if an unbalanced head "h" is applied to a cross-sectional area "a" of a mass of water which a length, "L," the resulting rate of change of velocity of the water will be 🍄 and the rate of change of discharge past a given point will

$$\frac{q_1}{t} = \frac{g_{1_{j_k}}}{r_1} \frac{s_1}{r_1}, \quad \text{(where } \frac{q_1}{t} \text{ is average rate of change of discharge in the } \\ \text{first reach of sever during the time period "t.,")}$$

$$\frac{q_1}{t} = \frac{g a_1}{2L_1} (h_{1b} + h_{1e}) \qquad (2)$$

$$\Delta Z_1 = \frac{t}{A_1} (q_1 - \frac{q_1}{2} - q_0)$$
, and(5)

Substituting from (5) and (6) in (4) gives

Substituting (7) in (2) with ΔF_1 replaced by $C_1 q_1$ and rearranging terms gives

$$\frac{t}{A_1} (q_1 - q_0 - \frac{q_1}{2}) + 2h_{1b} - c_1q_1 + \left[(q_1 - t_2 - \frac{q_1}{2}) - (q_2 - \frac{q_2}{2}) \right] \frac{t}{A_2} = \frac{2q_1L_1}{4m_1}$$
 (8)

$$\left[(q_2 - \frac{q_2}{2}) - (q_1 - I_2 - \frac{q_1}{2}) \right] \frac{t}{k_2} + 2h_{2b} - c_2q_2 + \left[(q_2 - I_3 - \frac{q_2}{2}) - (q_3 - \frac{q_3}{2}) \right] \frac{t}{k_3} = \frac{2q_2t_2}{4gq_2} - \dots$$
 (9)

It has been assumed that the upstress surge tank in the system (the nth tank) is connecte alysis similar to that above the following equation for this reach of sever is derived:

$$\left[\left(q_{n} - \frac{q_{n}}{2} \right) - \left(q_{(n-1)} - I_{n} - \frac{q_{(n-1)}}{2} \right) \right] - \frac{t}{A_{n}} + 2h_{nb} - C_{n}q_{n} = \frac{2q_{n}L_{n}}{4q_{n}}$$
 (10)

DERIVATION OF BASIC EQUATIONS

(2)	$-q_1(\frac{30}{50.7}) + q_1(\frac{20}{50.7} + \frac{1}{56.5} + \frac{1.4}{1200})$	$-q_1 \frac{10}{50.7} = \frac{20}{50.7} (2Q_2 - Q_3 - Q_3)$	+ 2h ₃₄ + U
(3)	$-q_3(\frac{10}{50.7}) + q_3(\frac{20}{50.7} + \frac{1}{32.5} + \frac{3.6}{1200})$	$-q_4 = \frac{10}{50.7} = \frac{20}{50.7} (2Q_5 - Q_5 - Q_4)$	+ 2h ₂₄ = V
(4)	$-q_s(\frac{10}{50.7}) + q_s(\frac{20}{50.7} + \frac{1}{32.5} + \frac{3.2}{1200})$	$- q_{g} \frac{10}{50.7} = \frac{20}{50.7} (2Q_{g} - Q_{g} - Q_{g})$	+2h ₄₀ • ¥
(5)	$- q_s(\frac{10}{50.7}) + q_s(\frac{20}{50.7} + \frac{1}{65.0} + \frac{1.8}{1200})$	$- q_a \frac{10}{50.7} = \frac{20}{50.7} (2Q_a - Q_a - Q_a)$	+ 2h _{f1} . X
(6)	$-q_g(\frac{10}{50.7}) + q_g(\frac{10}{50.7} + \frac{1}{32.8} + \frac{4.2}{1200})$	$= \frac{20}{50.7} (Q_s - Q_s)$	+ 2h 4 + Y

		Evaluation of Constants						
	tga,	= 20 × 32. 2 × 90 = 36. 4						
	L,	1990 = 30.4						
	tga,	20 × 32.2 × 202 = 113						
10	ī,	1150						
51	***	20 - 22 2 - 202						

		Discharge in C.F.S.				L = 1590 = 36.4			
	Time in Seconds	. Q,	Q,	Q,	Q,	Q,	Q,	tga.	20 x 32, 2 x 202
-	o	1800.0000	1800.0000	1800.0000	1800.0000	1800.0000	1800.0000	1.	1150 = 113
i	20	1671, 3672	1708.0380	1735,9129	1752.8154	1761, 7193	1767, 3461	tea. 20	20 × 32.2 × 202
	40	1457, 1888	1489. 2326	1525, 6467	1557.0291	1577.9418	1592. 3715	~ -	2000 = 65
with head losses	. 60	1241.8593	1243, 7307	1240, 5154	1239, 1219	1240.6706	1242.5272		
1	80	925. 1725	931,8787	935, 1374	927,6441	917.2296	908.7364	tge_	20 × 32, 2 × 202 = 65
	100	583,7772	592. 5277	606.9404	627.8387	645, 1935	657.8787	L,	2000
	120	277.7281	290.6151	296.9773	298.9728	30 2, 3896	305, 6356	tea,	20 × 32.2 × 202 = 130
	140	- 36. 7388	-46.9904	-53.0575	-63, 1278	-77.6819	-90. 1417	L,	1000
without head losses	160	- 392. 8596	-401.4110	- 413, 3055	-414, 4202	- 406. 3025	- 398, 1858	tgs,	20 x 32. 2 x 202 = 65.6
<u> </u>	180	-711.4705	-710.7176	- 703. 394 7	-702.6834	-706.1207	-709.3973	T,	1980
									····

LOUISVILLE PLOOD PROTECTION PROJECT SOUTHERN OUTFALL SEVER SURGE ANALYSIS FOR SHUTDOWN OF FLOW IN MODEL SEVEN

445.8

446, 909622

450.865730

454.078027

452, 769033

453, 59 58 57

456.738105

454.920788


454,064161


455.018815

Constant Level Pool

Elevation 450.0

ORIO RIVER BIVISION Computed by P.F.B. Checked by R.L.I.





HYDROGRAPH FROM MODEL TESTS SHUTDOWN OF FLOW IN MODEL SEWER

APPENDIX B

ANALYSIS OF SURGES IN SOUTHERN OUTFALL SEWER (PROTOTYPE)
by F. U. Druml and H. B. Willis*

(November 1950)

General

Southern Outfall Sewer drains a large portion of the central urban area to be protected by the Louisville, Kentucky, Flood Protection Project. State Fairgrounds Pumping Plant is planned to pump flood period runoff carried to the line of protection by this sewer when drainage by gravity is blocked by high river stages. This plant will pump combined storm runoff and industrial and sanitary sewage from an area of over seven square miles against static heads ranging from 11 to 67 ft. With the pumping plant operating at or near design capacity, flow conditions in Southern Outfall Sewer will be especially conducive to development of large surges in the pumping plant sump, the main sewer, connecting sewers and manholes, if the pumping plant discharge is suddenly decreased or stopped altogether. Therefore, considerable study has been given to analyses of surges that could develop under various operating criteria in order to evaluate conditions that could develop so as to determine a practicable method for alleviating these surges. This method would then be incorporated into design of the pumping plant and other planned work. The basic report describes surge tests in a greatly simplified model of part of Southern Outfall Sewer in which surges were produced by sudden closure of a valve at the outlet end of the model sewer. Appendix A describes the development of a method for analytically determining surge heights in a simple sewer system, and shows that surges computed by this method for the model sewer compare very favorably with the surges measured in the model tests. The method of computing surges in the prototype sewer is described in the following paragraphs.

^{*} Louisville District and Office, Chief of Engineers, respectively.

Southern Outfall Sewer

The areas served by the major sewer systems in the western portion of Lousiville are shown on plate Bl. Southern Outfall Sewer, which is the second largest sewer in the city system, is within this group. is estimated that a sewered area of about 4,540 acres served by this sewer will contribute storm runoff to the planned State Fairgrounds Pumping Plant within a short time after beginning of rainfall. shown on plate B2. In addition to the 4,540-acre area, an area located near the eastern limits of the sewer system slowly drains into Southern Outfall Sewer through ditches. Because of the very slow runoff from this area, it has been neglected in determining the pumping capacity required at State Fairgrounds Pumping Plant. The drainage area is flat with considerable variation in development. About 75 per cent of the area contains residential developments, 5 per cent commercial developments and 17 per cent industrial developments. The remainder is in parks, cemeteries, and other open spaces. The population of the area served by Southern Outfall Sewer is about 60,000 persons. The area is drained by a welldeveloped system of sewers, as shown on plate B2. The main sewer, a profile of which is shown on plate B3, is built of reinforced concrete and consists of horseshoe and semielliptical sections of varying sizes. The largest of these is a 15-ft-6-in. x 15-ft-2-in. horseshoe section, which is 3,247 ft long and flows into a sewer of smaller section approximately 1500 ft landside of the line of protection. This next section of sewer is considerably smaller but is on a steeper grade and has a brick paved invert. In addition to runoff from the drainage area shown on plate Bl, Southern Outfall Sewer carries sanitary or dry weather flows from the areas to the north that are drained by Western Outfall and Northwestern Trunk Sewers. The dry weather flows of these two sewers reach Southern Outfall Sewer through Western Interceptor at a point approximately 1500 ft landward from the line of protection. At various points near the perimeter of Southern Outfall Sewer drainage area there are sewers that interconnect this area with other sewer systems. However, the probable amounts of flow through these interconnections during

periods of intense rainfall are so small compared to the flow that will reach State Fairgrounds Pumping Plant that these interconnections have been neglected in determining station capacity.

Planned Pumping Capacity

3. Since construction of Southern Outfall Sewer in 1910, the area served has been extended by construction of tributary sewers and has undergone intensive development. As a result, the sewer is now overloaded and, even with low river stages, intense storms frequently produce damaging hydraulic gradients and flooding along several reaches of sewer. Flood-period design rainfalls ordinarily used for determining pumping requirements for interior drainage would cause considerable damage in the area drained by Southern Outfall Sewer because of the inadequate sewer capacity now provided. For this reason the planned pumping capacity at minimum design head for the State Fairgrounds Pumping Plant is based, not upon design rainfall criteria as used at other plants, but on the maximum flow that the existing sewer can deliver to the pumping plant without producing excessive damage within the protected area. fully utilize the capacity of the existing sewer and to provide as high a degree of protection as possible with the conditions that exist, it is planned that during pumping periods the hydraulic gradient at the pumping plant intake will be held at or below the crown of the existing sewer. Computations based upon a value of Kutter's "n" of 0.013 for the main sewer indicate that the maximum discharge that the sewer can deliver to the pumping plant under these conditions without producing considerable damage in the protected area is about 1700 cfs. However, in order to allow an additional margin of safety, it is planned to provide 1800-cfs pumping capacity at minimum design head at State Fairgrounds Pumping Plant. As mentioned above, the computations of discharge capacity of Southern Outfall Sewer were based upon a value of Kutter's "n" of 0.013, which is commonly used for design of concrete sewers. However, measurements of discharge in the 15-ft-6-in. by 15-ft-2-in. concrete horseshoe section of this sewer indicate that a value of "n" of 0.016 would be more

applicable to this section. Rainfall criteria normally used to determine pumping capacities at maximum design heads would not result in runoff rates that exceed the capacity of Southern Outfall Sewer. The required capacity of the State Fairgrounds Pumping Plant at maximum design head based on these criteria is 910 cfs. The computed hydraulic gradient in the main sewer for 1800-cfs inflow to the pumping plant is shown on plate B3. This profile is based upon uniform contribution of runoff from the tributary sewered area. It will be noted that the computed hydraulic gradient on plate B3 shows that approximately 33,000 ft of the main sewer will be surcharged when the inflow to the pumping plant is 1800 cfs. Under these conditions the velocities in the surcharged sections of sewer would be as high as 20 ft per sec (in 10-ft-7-in. by 10-ft-1-1/2-in. sewer near pumping plant). The kinetic energy of the large mass of water moving at high velocities through surcharged sewers introduces the possibility of large surges developing upon pump shutdown.

Generalized Model of Prototype Sewer

4. The analytic method of determining surge heights described in appendix A assumes that the sewer is divided into reaches with the sewer barrel in each reach having a uniform cross-sectional area, and that the rate of flow at any instant is constant throughout each individual reach. The method also assumes a surge tank located between adjacent reaches of sewer with the cross-sectional area of each tank representing the combined horizontal areas of any manholes in the reach or partially filled tributary sewers connecting with the reach that would afford surge relief. By this method, determination of the surges during each short time interval requires the solution of a group of simultaneous algebraic equations, one equation for each reach of sewer in the system. From examination of the plan and profile of Southern Outfall Sewer shown on plates B2 and B3, it is obvious that it would not be practicable to analyze surge action in this sewer by the above-described method if each inflow point, change of sewer section, or opening in the sewer section, or opening in the sewer barrel is considered separately. For this reason

analysis has been based upon a hypothetical sewer system, differing considerably from the prototype but having essentially the same characteristics insofar as the effect upon surge action is concerned. In developing the hypothetical system, several lengths of sewer having slightly different cross-sectional areas and rates of discharge have been considered as one reach having a length equivalent to the corresponding reach in the prototype, but with cross-sectional area and initial rate of discharge roughly equivalent to the weighted averages of the areas and initial discharges of the respective lengths of the reach of prototype sewer. To facilitate computations, the hypothetical system was made as simple as possible without departing too much from those characteristics of the prototype sewer that influence surge heights. For example, since surge is a function of the kinetic energy of moving water in the sewer system, it is apparent that in computing surge heights at points near the river, the kinetic energy of water in small laterals and near the upper end of the main sewer may be neglected if this energy is a very small part of the total energy in the system. With 1800-cfs inflow to the pumping plant, the kinetic energy of the water in all the surcharged laterals would be but a small part of the total kinetic energy of the water in the main sewer. Therefore, surge computations were not extended to the laterals, but the laterals were considered to discharge directly into the surge tanks of the hypothetical sewer system. It was also found that the kinetic energy of water contained in the surcharged main sewer upstream from Third and Avery Streets (point 6 on profile on plate B3) was less than one per cent of the total energy in the system with a pumping plant inflow of 1800 cfs. Thus, surge computations have not been extended upstream from this point, but it has been assumed that a constant level headwater reservoir is located at point 6 on the main sewer. hypothetical sewer system adopted for the computation of surge heights includes five surge tanks and a constant level reservoir as shown on plate B5. Initial water-surface elevations and discharges required for the computation of surge heights resulting from complete shutdown of the pumping plant from 1800 cfs are also shown.

Method of Analysis

5. The method of determining surge heights provides for the progressive calculation of surges in all risers in the system during successive time intervals. Derivation of basic equations for this method of analysis from the general laws of motion is shown on plate Al in appendix These basic equations express changes in flow in each reach of sewer for a short interval of time in terms of elements of the sewer system, physical constants, length of time interval, and, also, the discharges, water-surface elevations, and hydraulic losses that exist at the beginning of the period. One such equation is derived for each reach of sewer in the system. Thus, for a sewer system with five risers the changes in flow in each reach within a short time interval are expressed by five simultaneous linear equations involving the five unknown changes in dis-It will be noted that, in order to make the basic equations linear, hydraulic losses between surge tanks are assumed as linear functions of discharge. This, of course, is not true, but such an assumption permits the simplification of the computation procedure and, in the usual case, the errors resulting from this assumption will not greatly affect the computed surge heights. Application of the analytic method to computation of surges that would result from total plant shutdown from 1800 cfs is shown on plate B5. In this and other surge computations it has been assumed that pump discharge would cease instantaneously, although it is known that, owing to inertia of the moving parts of the pumping units and the water within the pump passages, pump discharge would not stop immediately. However, in the model tests of surges described in the basic report, it was found that within certain limits variation in time for complete stoppage of pump discharge made no appreciable differences in the height of surges produced. It will be noted that computations in this example have been carried to several more significant figures than would be justified by the basic data and the nature of the problem. This was done to facilitate arithmetical checks for each interval of time in the computations. In all of the computations of surges in Southern Outfall Sewer the time interval used in the step-by-step computations was 20 sec,

as this interval was found adequate to properly define the surges in this system without requiring an excessive amount of computation. As shown on plate B5, sheet 3, a cross-check on the computations is provided at the end of each successive time interval if the increment of surge in the most downstream tank computed from the basic equations is compared with the increment of surge based on the volume of water entering or leaving the surge tank during the same time interval.

Surge Relief Reservoir

6. Some of the extremely high surges measured in the model tests would not occur in the prototype sewer because the surges measured in the model were generally confined in surge tanks while such surges in the prototype would be higher than the ground surface and would not be confined. However, the model tests and preliminary surge computations indicated that with Southern Outfall Sewer as it now exists there are possibilities of large and possibly destructive surges developing in the pumping plant sump and along the lower reaches of the main sewer during pumping periods. High or moderately high surges could be developed under certain circumstances not only from total shutdown of pumping plant, but also from shutdown of individual pump units. It was found that the pumping plant itself could be protected from damage due to surges in the sump by installation of surge relief valves or flap gates which would open and allow discharge direct to the river during high surges. ever, because of the great depth of the planned station, it would be difficult and expensive to install these valves at an elevation low enough to provide surge relief in the protected area. Also, these valves would not be effective in preventing surges at high river stages. these circumstances, it appears that the only method of effectively protecting the pumping plant from damage by surges and at the same time alleviating surges in the main sewer within the protected area consists in providing a surge tank or surge relief reservoir connected to the sewer as close to the pumping plant as possible. This surge relief reservoir would function in the same manner as the simple surge tanks frequently

constructed where long penstocks are used at hydroelectric installations. Fortunately, a site for the development of a surge relief reservoir is available adjacent to Southern Outfall Sewer in the now abandoned channel of Upper Paddy Run within the Kentucky State Fairgrounds. at this site is shown on plate B4. In this low area a reservoir with sufficient storage area to provide effective surge relief can be provided with little excavation by constructing a short levee across the abandoned creek channel. An outlet structure with sufficient capacity to allow high rates of flow from the sewer into the surge relief area with small loss of head will be required. Investigations indicated that, if possible a surge relief reservoir at this site should have about 90,000 sq ft of horizontal area, as a much smaller reservoir would not prevent the development of fairly large surges in the pumping plant sump upon shutdown of individual pump units. It appears practicable to develop a reservoir with about 90,000 sq ft of horizontal area at the State Fairgrounds site and such a reservoir is tentatively planned. Computations of surges for total plant shutdown from 1800 cfs discharge rate, which are shown on plate B5, sheets 1 and 3, are based on a 90,000-sq-ft surge relief reservoir.

Results of Analyses

7. As now planned, State Fairgrounds Pumping Plant will have four large pumping units with 386-cfs capacity each at minimum design head, and two smaller units, each having 128-cfs capacity at minimum design head. Surge analyses have been made for complete plant shutdown when pumping at rated capacity at minimum head (pump plant discharge changing from 1800 cfs to zero), for shutdown of one large pump unit under the same conditions (pump discharge changing from 1800 cfs to 1414 cfs), and for shutdown of one small pump unit (pump discharge changing from 1800 cfs to 1672 cfs). Computed water-surface elevations in risers of the hypothetical system with a 90,000-sq-ft surge relief reservoir in the State Fairgrounds for the first five minutes after complete plant shutdown are shown on plate 5, sheet 4. The table on the following page

shows computed maximum surge heights at the pumping plant sump and at the 90,000-sq-ft surge relief reservoir in the State Fairgrounds for complete plant shutdown from 1800 cfs, for shutdown of one large pump unit when inflow is 1800 cfs, and for shutdown of one small pump unit under the same conditions. It should be noted that the computed surges listed are maxima that would occur in the first four or five minutes after change It can be seen that, if it is assumed that the inin pump discharge. flows to the sewer system remain constant as was done in the surge computations, there would be a gradual filling of the sewer system and connecting low areas because of the storage of inflow. This gradual filling, if continued long enough, could produce higher water-surface elevations than caused by the surges due to kinetic energy of the flowing water. However, records of storm discharge in Southern Outfall Sewer show that peak discharges are of relatively short duration, and, for this reason, flooding from continued sewer discharge would not be as rapid as indicated by the surge computations.

COMPUTED MAXIMUM SURGE HEIGHTS WITH 90,000-SQUARE-FOOT SURGE RELIEF RESERVOIR IN STATE FAIRGROUNDS (Pumping Plant Inflow = 1800 cfs)

Operating Condition	Maximum Height of Surge in Pumping Plant Sump, ft	Maximum Height of Surge in Surge Relief Reservoir, ft			
Complete shutdown of pumping plant	32	4			
Shutdown of one large (386 cfs) pumping unit	7	1			
Shutdown of one small (128 cfs) pumping unit	2.6	0.3			

Possibility of Surge Development

8. Most of the pumping at the State Fairgrounds Pumping Plant will be accomplished under conditions that will not be conducive to surge development upon shutdown of pumping units. The pumping plant

will be operating at high capacity with the attendant surcharge of a considerable part of Southern Outfall Sewer very infrequently. A long reach of surcharged sewer carrying runoff at high velocities is necessary before surges develop in the magnitude of those listed above. timated that a pump plant discharge of 1800 cfs, upon which the computed surges discussed above are based, will occur once in about 25 years on the average. There is little probability of complete shutdown of the pumping plant when pumping at or near maximum capacity. In the design of the plant and its power supply system every practicable safeguard to insure dependable operation will be included. As now planned, power will be supplied to the plant by two three-phase circuits from the Paddy Run Generating Plant of the Louisville Gas and Electric Company, which is located about one mile downriver from the pumping plant site. ever, it is possible that inadvertent misoperation at the pumping plant or at the generating plant or a power outage due to transmission line or transformer failure will cause unintentional complete plant shutdown. such a shutdown should occur as a result of misoperation, it is possible that the pumps could be placed in operation again before serious surge developed. The computations indicate that under certain conditions fairly large surges will develop after the shutdown of one large pumping unit. However, the pumping schedule is to be arranged so that, as the pumps are progressively shut down after a period of high inflow, the maximum sudden decrease of pump discharge will be equivalent to the capacity of one of the smaller pumps. In other words, when it becomes necessary to stop a large pump, the two 128-cfs pumps will be started at the same time.

Conclusions

9. It is estimated that the planned pumping plant could be protected from possible damage due to surge action following complete plant shutdown by installation of high-level surge relief valves in the sump walls at lower cost than by construction of a surge relief reservoir in the State Fairgrounds. However, the surge relief valves would afford

little protection against damages from such surges in the area within the protection works and would not alleviate smaller surges in the pumping plant sump and in Southern Outfall Sewer that could develop during ordinary pumping operations. Since there is little probability of complete plant shutdown when the plant is operating at or near maximum capacity, construction of a surge relief reservoir solely to protect the interior area against damages from such an occurrence may not be justi-However, the computed surges for shutdown of one pumping unit without a surge relief reservoir indicate that rapid changes in sump level would probably make plant operation very difficult and that surges in the main sewer and its laterals might cause some damage in the protected area. For these reasons it is considered that the surge relief reservoir should be provided to insure reasonably satisfactory operating conditions at the pumping plant under all conditions. As indicated by the computed maximum surge heights listed in paragraph 7, even with the planned surge relief reservoir the surges in the pumping plant sump for shutdown of a single pumping unit may cause difficulty in programming pump operation. For this reason consideration is being given to basing the pump operation schedule upon stages at the surge relief reservoir rather than on stages in the pumping plant sump because of the smaller amplitude of the surges in the reservoir.








PLATE B









Equations to Seven Significant Figures:

q1 - -15.51384U -.01467165V -.0005506610W --000005260578X -.0000006902498Y -.003051808x -8.5114347 -.3194538W -.00040043321 q3 = -.0005506610U -.3194539V -8.832085W -.08437472x -.01107096**Y** - ~.000005260578tt -.003051808V -.08437472W -7.022412X -.9214232Y -.00000069024980 -.00040043327 -.01107096W -.9214232X -4.713314Y

COMPLETE SHUTDOWN OF STATE FAIRGROUNDS PUMPING PLANT

(1800 CFS TO 0 CFS)

Time in Seconds	6.6	.0094 1169,9906 .0941 1169,8365 .4598 1169,4367 1.4868 1167,9499 3.6142 1164,3357 7.0934 1177,2423 11,7453 1145,4970 16,8677 1128,6293 21,3681 1107,2612 24,0928 1083,1684 24,2316	939.9999 530. 939.9987 529. 939.9910 529. 939.9910 529. 939.9578 529. 1060 939.8518 529. 2713 939.8505 529. 10958 937.9005 528. 10958 937.9005 528. 1,8053 1. 936.6662 527. 2,8262 233.2346 525.	0000 0 0000 20 0000 20 0002 998 40 0015 9983 60 0085 898 80 0340 100 072 4486 120 7791 6695 140 2214 481 160 1119 3362 180 096 2266 200		h ₂ 0 .02665718 .1393760 .3635872 .6545042 .9277336 1.101672 1.133212 1.033546 .860313 .691807 .595095	h ₃ 0 .00098268 .00881134 .03905746 .1157222 .2605124 .4779024 .7447730 1.011141 1.213267 1.294781 1.227717	.00012260 .00074638 .00299134 .00893988 .02158966 .04413448	h ₅ 0 .0000212 .00002562 .00024644 .00127470 .00482174 .01437790 .03562766 .07571982 .1414184 .2365710 .3600630					
(1) Time in .0002222 Seconds 0 20 .35333	00974	6032 Q 1 Col (1	Co1 (3) .)+(2) .0466666	211 = (0)	(Q ₃ - Q ₂)	(6) x 8510638 (Q ₁		8) x 22222 <u>Col</u>	(7)+(9) Co1 3.5	11) (12) (10) + Col (11) - 27801 2h ₂ = (V)				
20 .35333 40 .35327 60 .35292 80 .35187 100 .34674 120 .34642 140 .3221 160 .33748 180 .33293 200 .32896 220 .32571 240 .32301	74 -14.955 93 -8.491 47965 01 5.236 27 8.421 76 8.281 17 5.545 87 1.557 79 -2.145 36 -4.576	.893 -8.14 .6294157 .5402 5.58 .680 8.76 .702 8.62 .702 5.88 .761 1.92 .761 1.92 .7656 -1.82 .7856 -1.82	760 -14.5509 1964 -8.0952 44194 5.6328 7503 8.8141 3870 8.6705 6732 5.9333 0700 1.9673 00288 -1.7736 1270 -4.2046	-42.69871 -7 -50.05696 27 -40.75801 9 -21.06129 0 .923950 7 18.07434 19 26.20292 24.71801 22 16.05822 33 4.32770	-419.7579 -3 -418.2855 -3 -413.9998 -3 -405.8808 -3 -394.5664 -3 -382.5121 -3 -373.1710 -3 -369.5951 -3 -373.0944 -3 -382.5428 -3	.572408 -5; .559876 -716; .5523402 -148; .154305 -211; .358012 -242; .255422 -238; .175923 -208; .175271 -125; .255683 -99	0.0000	17780 -3.5 347 -3.7 540 -3.8 368 -3.5 342 -3.8 1013 -3.7 1119 -3.6 1417 -3.5 1620 -3.1	18478605 1911119 15415633 28344236 18644636 18642325 3993511 555233 .07 477035 .05	0,569851102994 11310470062 16355 -1.053529 1956410 -1.704649 18645 -2.224112 186622 -2.461966 121340 -2.378558 13169 -2.053923 12568 -1.648058 10766 -1.332848 14511 -1.224701				
(1) Time in Seconds (Q ₂ - Q	(2) Col (1) x .008510638	(3) $(\mathbf{q_{i_4}} - \mathbf{q_3})$	(4) Col (3) x .002721088		ol (s) Col	7) (6) - = (W)								
0 20 420.000 419.757 60 418.265 80 413.995 100 405.88 120 394.566 140 382.512 160 373.171 180 369.595 200 373.094 220 382.542 240 394.632	9 3.572408 5 3.559876 8 3.523402 8 3.454305 4 3.358012 1 3.255422 0 3.175923 1 3.175271 8 3.255683	-230,0000 -229,9907 -229,8978 -229,4457 -227,9921 -224,4639 -217,6618 -206,5007 -190,7288 -171,2010 -149,9344 -129,7352	6258502 6258249 6255722 6243419 6203866 6108404 5922769 5619066 5189898 4658530 4079847 3530209	2.946583 2.934304 2.899960 2.833918 2.747172 2.663145 2.614016 2.626500 2.709418	0143140 0495581 1147003 2014467 285473 -1.2 334602 -1.8 322118 -2.3 239200 -2.6 100920 -2.6	1040004 31937 27673 46144 22471 41278 241148 44400 65734 990482 98500								
(1) Time in Seconds (93 - 9	(2) Col (1) x .002721088	$\frac{(3)}{(\mathbf{Q}_5 - \mathbf{Q}_{\mathbf{L}})}$	(4) Col (3) x .05714286 C		ol (5) + Col	(6) -	8) (9 - Q ₅) ^{Co1} (- O571	3) x Col	(9) - Col (1	10) -				
20 230.000 40 229.990 60 229.897 80 229.449 120 224.483 140 217.661 160 206.500 180 190.726 200 171.201 220 149.934 240 129.735	7 .6258245 8 .625572: 7 .6243419 11 .6203866 9 .5108401 8 .5922765 7 .5619066 8 .5189896 0 .4658536	-409,9999 -409,9989 -409,9680 -409,9680 -409,7319 -409,7319 -408,7319 -408,3240 -407,6074	-23.42857 -23.42816 -23.42816 -23.42674 -23.42623 -23.41325 -23.3582 -23.3580 -23.29185 -23.9185	12.80274 12.80294 12.80382 12.80635 12.81179 12.82097 12.83391 12.84972 12.86695 12.88387	000220 001100 003630 009070 018250 031191 047002 064233 081154	0004 409. 0004 409. 0059 409. 0961 409. 6143 409. 1946 409. 19530 408. 2004 408. 6129 407. 2320 406.	9999 23.4 9989 23.4 9680 23.4 8960 23.4 7319 23.4 4268 23.3 3240 23.3 36074 23.2	2857 0 285100 281600 267400 226300 258200 258200 258200 258000 258000 258000	0183004 0594015 1532042 3275104 5986213	090 438 5558 408 401 430 3861 986				
Time in (1) Seconds -15.5138						7165V <u>-8.511</u>	434V31945		51808v000l	(5) (1) 4004332V0005506				(5) 01107096W
20 265, 951 40 662, 421 60 776, 575 80 632, 313 100 326, 741 120 -14, 334 140 -280, 406, 507 180 -383, 471 200 -249, 124 220 -67, 135 240 97, 583	0 .6264605 17 .7344182 2 .5979873 5 .3090039 01 -01355587 4 -2651804 9 -3844401 3 -3626540 7 -2356006	.00943990 .02351251 .02756442 .02244385 .01159763 .00050878 .00995283 .01442893 .01361124 .00884264 .00238310	000046 0000950 0001378 0001300 0000844 0000227	.0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000 .0000	2947 .0016 3455 .0068 2813 .0154 1454 .0250 10064 .0326 1248 .0361 1809 .0348 1108 .0241 10299 .0195	9659 4.000 5701 8.967 11001 14.509 3139 18.930 2110 20.954 17.481 17.481 17.481 17.481 17.481	902 .15016 043 .33655 01 .54455 38 .71050 86 .78648 94 .75983 83 .65613 34 .52647 45 .42578	19 .0031 18 .0051 13 .006 16 .0071 17 .0061 18 .0050 18 .0050	43454 .000 21517 .000 20226 .000 78756 .000 51345 .000 25890 .000	000417 018823 000017 068267 00017 068260 00019 998585 00068 095245 00160 082246 001290 055994 001487 053372 001483	59 01020244 30 0407856 61 1105770 84 2307961 52 3365310 49 5827310 97 7489275 92 8515789 54 8594847	0 .282070 3 1.127619 3.057173 6.380925 10.96307	0 .00033753 .00269468 .01077237 .02920580 .06095829 .1047325 .1539120 .1978081 .2249206 .2270087 .2023728	0 .00004429 .00035357 .00141346 .00383215 .00199845 .01374214 .02019507 .025951263 .02951223 .0295622 .02655370
0	260578x0030		3) (4) 37472X -7.0224					096Y92	4) (5) 14232 Y <u>-</u> 4.713	$\frac{\Sigma (1) = q_1}{}$		$\frac{\Sigma (3) = q_3}{\Sigma (3)}$	$\frac{\Sigma (h) = d^{h}}{\Sigma (h)}$	$\frac{\Sigma(5)}{\Sigma(5)} = q_5$
20 0 40 0 60 0 80 .0000 120 .0000 140 .0000 160 .0000 180 .0000 200 .0000 220 .0000 240 .0000	0005 .0000 0014 .0000 0032 .0003 0063 .0003 0108 .0005 0168 .0005	00790 .000 2933 .000 08225 .002 18747 .005 18459 .010 182654 .017 17670 .027	8108 .0674 2739 .1892 1831 .4313 079 .8389 3221 1.4417	.000\(\frac{124}{24}\) 0023\(\frac{36}{24}\) 0023\(\frac{36}{24}\) 0024\(\frac{32}{22}\) 0056\(\frac{603}{21007}\) 018916\(\frac{189168}{24892}\) 024\(\frac{324892}{2425043}\)	0 0 0 0 0 0 0 0 0 0 00000003 00000007 000000015 000000042	0 0 00000 00000 00000 00001 00004 00005 00015 00024	036 .0000 175 .0000 624 .0001 765 .0004 165 .0011 461 .0023 161 .0041 421 .0067	0996 .000 1849 .001 1249 .011 1801 .040 1150 .091 1930 .194 1158 .340 1174 .561	0 00101 .0009 0829 .0044 4036 .0206 4356 .0731 0616 .2077 5837 .4907 4697 .9953 3860 1.784 1939 2.8741 5517 4.2276	64 326.7667 433 -14.30098 763 -280.3656 232 -406.4720 233 -383.4399 51 -249.0991 -67.11821	.2515140 1.566545 4.745524 9.605824 14.92862 19.14771 21.08642 20.44364 17.86881 14.64445 12.14209	.00943990 .09408335 .4598375 1.466845 3.614187 7.093364 11.74527 16.86767 21.36812 24.09282 24.23164 21.64097	.0009018 .00117976 .00772355 .03322095 .1060448 .2713470 .5841569 1.095770 1.840343 2.826176 4.032363 5.409030	.0001183 .00151835 .00151835 .00848946 .03402429 .1071534 .2790815 .6211831 1.211851 2.109563 3.329820 4.829119

General Notes: Sheet 2 is used to evaluate (q)s from equations developed on sheet 1. These q values are the bases of determining water surface elevations (Z) shown on sheet 3.

Sheet 2 is used in conjunction with sheet 3. New values of Q and h are inserted as sheet 3 computations progress. The Q values for each period are determined by subtracting the retardation in discharge (q) from the Q values at the beginning of the preceding period. The h values shown are h_e values of the preceding period shown on sheet 3.

Values of Q and h at the beginning of the first period are known since the Q values are those for steady flow conditions at the instant of stoppage and all the h values are zero.

COMPLETE SHUTDOWN OF STATE FAIRGROUNDS PUMPING PLANT (1800 CFS TO 0 CFS)

The items shown in a typical 20-second computation are obtained as follows:

Cq (as shown)
summation of hydraulic loss changes of reaches upstream from tank during time period considered ΣΔF

he Σhb Σhe ΔZ

COMPLETE SHUTDOWN OF STATE FAIRGROUNDS PUMPING PLANT

(1800 CFS TO 0 CFS)

